STATE OF VERMONT
AGENCY OF TRANSPORTATION

# TRAFFIC SIGN SUMMARY SHEET 62

| MILE MARKER, STATION OR SIGN NUMBER | SIGN LEGEND | SIGN DIMENSIONS | | | NEW & SALVAGED SIGNS | | | | EXIST POST | | NEW SIGN POSTS | | | | | | | | | | | | | | | | | | | | | SIGN DETAIL | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | | FLANGED CHANNEL lb/ft | | | SQUARE STEEL (in) lb/ft | | | | | TUBULAR ALUMINUM DIA (in) lb/ft | | | TUBULAR STEEL DIA (in) lb/ft | | | | | W-SHAPE STEEL FTG. SIZE | | | | | | |
| | | E A | WIDTH (in) | HEIGHT (in) | "A" | "B" | SALV SIGN | SALV TIS | RETAIN | SALVAGE | NO. OF POSTS | 1.12 | 2.0 | 3.0 | 1.75 / 1.88 | 2.0 / 2.42 | 2.5 / 3.35 | ANCHOR | SLEEVE | 3.0 / 1.3 | 4.0 / 1.7 | 4.0Mod / 1.7 | FND-ATION | 3.0 / 7.6 | 3.5 / 9.0 | 4.0 / 10.8 | 5.0 / 14.6 | 24" | 30" | WEIGHT | POST SIZE | SIGN FRAME | REMARKS | DETAIL ON SHEET NUMBER | STD. SHEET NUMBER |
| 0.030 RAMP N-E LT | | 1 | 36 | 36 | 9.00 | | | | | | | | | | | | | | | | | | | | | | | | | | | | W11-2 | | |
| | | 1 | 30 | 18 | 3.75 | | | | | | 2 | | | | | X | | 2 | | | | | | | | | | | | | | | W16-7p | | |
| 0.030 RAMP N-E RT | | 1 | 36 | 36 | 9.00 | | | | | | | | | | | | | | | | | | | | | | | | | | | | W11-2 | | |
| | | 1 | 30 | 18 | 3.75 | | | | | | 2 | | | | | X | | 2 | | | | | | | | | | | | | | | W16-7p | | |
| 0.050 RAMP N-E LT | | 1 | 36 | 36 | 9.00 | | | | | | 2 | | | | | X | | 2 | | | | | | | | | | | | | | | W4-2R | | |
| 0.050 RAMP N-E RT | | 1 | 36 | 36 | 9.00 | | | | | | 2 | | | | | X | | 2 | | | | | | | | | | | | | | | W4-2R | | |
| 0.080 RAMP N-E RT | | 1 | 36 | 36 | 9.00 | | | | | | | | | | | | | | | | | | | | | | | | | | | | VR-046 | | E-142 |
| | | 1 | 36 | 36 | 9.00 | | | | | | 2 | | | | | | | | | | | | 2 | X | | | | | | | | | VR-002 | | E-142 |
| 0.160 RAMP N-E RT | | 1 | 30 | 30 | 6.25 | | | | | | 1 | | | | | X | | 1 | | | | | | | | | | | | | | | R3-2 | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| INT. I-189 / US 7<br>0.013 RAMP S-E RT | | 1 | 24 | 30 | 5.00 | | | | | | 1 | | | | | X | | 1 | | | | | | | | | | | | | | | W13-3 | | |
| 0.027 RAMP S-E LT | | 1 | 18 | 18 | 2.25 | | | | | | 1 | | | | X | | | 1 | | | | | | | | | | | | | | | OM1-1 | | |
| 0.030 RAMP S-E LT | | 1 | 24 | 12 | 2.00 | | | | | | | | | | | | | | | | | | | | | | | | | | | | M3-2 WHITE ON BLUE | | |
| | | 1 | 30 | 24 | 5.00 | | | | | | | | | | | | | | | | | | | | | | | | | | | | M1-1 | | |
| | | 1 | 21 | 15 | 2.19 | | | | | | 1 | | | | | X | | 1 | | | | | | | | | | | | | | | M6-2 WHITE ON BLUE | | |
| 0.039 RAMP S-E LT | | 1 | 36 | 36 | 9.00 | | | | | | | | | | | | | | | | | | | | | | | | | | | | W11-2 | | |
| | | 1 | 30 | 18 | 3.75 | | | | | | 2 | | | | | X | | 2 | | | | | | | | | | | | | | | W16-7p | | |
| | | | | | | | | | | | | FT | FT | FT | FT 9.5 | FT 193.5 | FT | | EA. | LB | LB | LB | | LB 191.6 | LB | LB | LB | | | | | | | |
| SUBTOTALS SHEET 62 | | | | | SF 96.94 | SF | EA. | SF | | | | FT | | | FT 203.0 | | | | | LB | | | EA. 2 | LB 191.6 | | | | EA. | EA. | LB | | | | |

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: WATERBURY - WINOOSKI
PROJECT NUMBER: IMG SIGN(18)

FILE NAME: 090124 tss int13 15.xls
PROJECT LEADER: CRB
DESIGNED BY: BDB
TRAFFIC SIGN SUMMARY SHEET # 62

PLOT DATE: 10/27/2009
DRAWN BY: SRB
CHECKED BY: DAM
SHEET 120 OF 174