STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 69

MILE MARKER, STATION OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (in) lb/ft 3.0 1.3	4.0 1.7	4.0Mod 1.7	TUBULAR STEEL DIA (in) lb/ft FND-ATION	3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
0.226 RAMP A RT		1	24	30	5.00						1					X		1														VR-602		
0.234 RAMP A RT		1	36	12	3.00						2					X		2														R6-1L		
0.240 RAMP A RT							1				2					X		2																	
0.023 RAMP B LT		1	30	30	6.25						1					X		1														R5-1		
0.023 RAMP B RT		1	30	30	6.25						1					X		1														R5-1		
0.023 RAMP B RT		1	30	24	5.00						1					X		1														VR-032		E-144
0.042 RAMP B RT		1	24	24	4.00																											VR-648		E-144
							1				1									X															
0.079 RAMP B RT		1	24	24	4.00																											VR-648		E-144
							1				1									X															
0.112 RAMP B LT		1	30	30	6.25						1					X		1														R5-1		
0.112 RAMP B RT		1 1	30	30	3.90 6.25						1					X		1														R1-2 36" X 36" X 36" BACK TO BACK R5-1		
0.115 RAMP B LT		1	36	12	3.00						2					X		2														R6-1R		
												FT	FT	FT	FT	FT 150.9	FT		EA.	LB 36.4	LB	LB		LB	LB	LB	LB								
SUBTOTALS SHEET 69					SF 52.90	SF	EA. 3	SF				FT			FT 150.9					LB 36.4			EA.	LB				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: WATERBURY - WINOOSKI
PROJECT NUMBER: IMG SIGN(18)

FILE NAME:	090124 tss restareas.xls	PLOT DATE:	10/27/2009
PROJECT LEADER:	CRB	DRAWN BY:	SRB
DESIGNED BY:	BDB	CHECKED BY:	DAM
TRAFFIC SIGN SUMMARY SHEET # 69		SHEET 127 OF 174	