

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES												TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
										ROADWAY	EROSION CONTROL	GRAND TOTAL	FNAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
										41		41		EACH	THINNING AND TRIMMING FOR SIGNS	201.31	EST.			
										1		1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST.			
										875		875		HR	UNIFORMED TRAFFIC OFFICERS	630.10	8			
										175		175		HR	FLAGGERS	630.15	2			
										1		1		LS	TESTING EQUIPMENT, CONCRETE	631.16	-			
										1		1		LS	MOBILIZATION/DEMOLIBILIZATION	635.11	-			
										1		1		LS	TRAFFIC CONTROL	641.10	-			
										4		4		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-			
										2		2		EACH	PORTABLE ARROW BOARD	641.16	-			
											8	8		LB	SEED	651.15	-			
											80	80		LB	FERTILIZER	651.18	-			
											1	1		TON	AGRICULTURAL LIMESTONE	651.20	0.7			
											1	1		TON	HAY MULCH	651.25	0.7			
											80	80		CY	TOPSOIL	651.35	4			
										8100		8100		SF	TRAFFIC SIGNS, TYPE A	675.20	0.66			
										12444		12444		SF	TRAFFIC SIGNS, TYPE B	675.21	0.75			
										52305		52305		LB	W-SHAPE STEEL SIGN POST	675.31	-			
										4556		4556		LB	TUBULAR ALUMINUM SIGN POST	675.32	0.2			
										36147		36147		LB	TUBULAR STEEL SIGN POST	675.33	0.8			
										9810		9810		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	0.2			
										114		114		EACH	FOUNDATION FOR W-SHAPE STEEL POST, 24 INCH DIAMETER	675.41	-			
										316		316		EACH	FOUNDATION FOR TUBULAR STEEL POST	675.43	-			
										1286		1286		EACH	REMOVING SIGNS (TYPE A)	675.50	-			
										127		127		EACH	REMOVING SIGNS (TYPE B)	675.50	-			
										36		36		EACH	ERECTING SALVAGED SIGNS	675.60	-			
										3375		3375		EACH	DELINEATOR WITH STEEL POST	676.10	EST.			
										2975		2975		EACH	REMOVAL OF EXISTING DELINEATOR	676.12	EST.			
										3		3		EACH	OVERHEAD TRAFFIC SIGN SUPPORT, MULTI-SUPPORT	677.13	-			
										10		10		EACH	SPECIAL PROVISION (FOUNDATION FOR W-SHAPE STEEL POST, 24 INCH DIAMETER)	900.620	-			

MODEL: Default

QUANTITY SHEET

PROJECT NAME: ROYALTON-MIDDLESEX

PROJECT NUMBER: IMG SIGN(19)

FILE NAME: z09a020quantity sheet.dgn PLOT DATE: 8/26/2009

PROJECT LEADER: CRB DRAWN BY: SRB

DESIGNED BY: BDB CHECKED BY: DAM

CLD REF. NO.: 09-0106 SHEET 5 OF 163