STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

MILE MARKER, STATION OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS E A	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 / 2.42	2.5 / 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (in) 3.0 lb/ft 1.3	4.0 / 1.7	4.0Mod / 1.7	FND-ATION	TUBULAR STEEL DIA (in) 3.0 lb/ft 7.6	3.5 / 9.0	4.0 / 10.8	5.0 / 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
22.730 NB	EMERGENCY STOPPING ONLY	1	48	36	12.00						2												2	X									R8-7		
22.805 NB	NORTH	1	30	15	3.13																												M3-1 WHITE ON BLUE		
	89	1	36	36	9.00																												M1-1		
	EISENHOWER INTERSTATE SYSTEM	1	36	36	9.00						1												1	X									M1-10		
22.900 NB		1	48	48	16.00																												VW-397	144	
	GROOVED SHOULDER	1	24	18	3.00						2										X												VP-396	144	
23.025 NB	SPEED LIMIT 65	1	48	60	20.00																												R2-1		
	MINIMUM 40	1	48	48	16.00						2												2		X								VR-141		E-142
23.210 NB	Randolph 11 Barre 29 Montpelier 31	1	114	48		38.00					2												2		X									132	
23.460 NB	KEEP RIGHT EXCEPT TO PASS	1	48	60	20.00						2										X												VR-132	144	
23.460 NB MED	KEEP RIGHT EXCEPT TO PASS	1	48	60	20.00						2												2	X									VR-132	144	
23.759 NB	ENTERING TOWN OF BETHEL	1	36	24	6.00						2					X		2															I-2		E-131
26.000 NB	MILE 2 6	1	12	36	~~3.00~~ 4.00						1					X		1															D10-2		E-139
26.053 NB	511 TRAVEL INFO	1	48	48	16.00						2												2	X										145	
26.668 NB	ENTERING TOWN OF RANDOLPH ORANGE CO.	1	36	30	7.50						2					X		2															I-2		E-131
27.000 NB	MILE 2 7	1	12	36	~~3.00~~ 4.00						1					X		1															D10-2		E-139
27.040 NB	TRAVEL INFO 100.1 FM	1	72	60		30.00					2										X													132	
												FT	FT	FT	FT	FT 86.1	FT		EA.	LB	LB 212.6	LB		LB 719.0	LB 613.8	LB	LB								
			SUBTOTALS SHEET 2		SF ~~163.63~~ 157.63	SF 68.00	EA.	SF				FT			FT 86.1					LB 212.6			EA. 11	LB 1332.8				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: ROYALTON - MIDDLESEX
PROJECT NUMBER: IMG SIGN(19)

FILE NAME:	090106_tss_main_NB.xls	PLOT DATE:	8/12/2009
PROJECT LEADER:	CRB	DRAWN BY:	SRB
DESIGNED BY:	BDB	CHECKED BY:	DAM
TRAFFIC SIGN SUMMARY SHEET # 2		SHEET 54	OF 163