STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 40

MILE MARKER, STATION OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (in) 3.0 lb/ft 1.3	4.0 1.7	4.0Mod 1.7	TUBULAR STEEL DIA (in) FND-ATION	3.0 lb/ft 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
0.301 RAMP B LT	STOP / DO NOT ENTER	1	30	30	6.25																												R1-1		
		1	30	30	6.25																												BACK TO BACK		
																																	R5-1		
	ONE WAY / ONE WAY	1	36	12	3.00						1					X		1															R6-1L		
		1	36	12	3.00																												BACK TO BACK		
																																	R6-1R		
0.301 RAMP B RT	STOP / DO NOT ENTER	1	30	30	6.25																												R1-1		
		1	30	30	6.25																												BACK TO BACK		
																																	R5-1		
	ONE WAY / ONE WAY	1	36	12	3.00						1					X		1															R6-1L		
		1	36	12	3.00																												BACK TO BACK		
																																	R6-1R		
INT #4 0.070 RAMP C RT		1	36	36	9.00						2					X		2															W3-1		
0.110 RAMP C RT	EAST WEST TO	1	24	12	2.00																												M3-2 GREEN ON WHITE		
		1	24	12	2.00																												M3-4 GREEN ON WHITE		
		1	24	12	2.00																												M4-5 GREEN ON WHITE		
	VERMONT 66 / VERMONT 66 / VERMONT 12	1	24	24	4.00																												M1-5		E-136B
		1	24	24	4.00																												M1-5		E-136B
		1	24	24	4.00																												M1-5		E-136B
		1	21	15	2.19																												M6-1L GREEN ON WHITE		
		1	21	15	2.19						2										X										#3	M6-1R GREEN ON WHITE		
		1	21	15	2.19																												M6-1R GREEN ON WHITE		
0.150 RAMP C RT	VT TECHNICAL COLLEGE / VERMONT VETERANS MEM CEMETERY	1	72	12	6.00																												D1-1		E-123
		1	72	20	10.00																												D1-2		E-123
	RANDOLPH 3	1	72	12	6.00						2										X											D1-1a		E-123
0.190 RAMP C LT	WRONG WAY	1	36	24	6.00																												R5-1a		
		1	24	24	4.00						2					X		2															R9-4a		
0.190 RAMP C RT	GAS 3 / DIESEL / WRONG WAY	1	72	10	5.00																												VD-502G		E-133
		1	72	10	5.00																												VD-502G		E-133
		1	36	24	6.00																												R5-1a BACK TO BACK		
	FOOD / LODGING 2	1	72	10	5.00																												VD-502F		E-133
		1	72	10	5.00																												VD-502L		E-133
	HOSPITAL 3 / 1 CAMPING 5	1	72	10	5.00						2										X											VD-502H		E-133
		1	72	10	5.00																												VD-502C		E-133
												FT	FT	FT	FT	FT 89.6	FT		EA.	LB	LB 192.8	LB		LB	LB	LB	LB								
SUBTOTALS SHEET 40		SF 138.57	SF	EA.	SF							FT			FT 89.6					LB 192.8			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: ROYALTON-MIDDLESEX
PROJECT NUMBER: IMG SIGN(19)

FILE NAME: 090106_tss_int4.xls
PROJECT LEADER: CRB
DESIGNED BY: BDB
TRAFFIC SIGN SUMMARY SHEET # 40

PLOT DATE: 8/12/2009
DRAWN BY: JH
CHECKED BY: DAM
SHEET 92 OF 163