STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 49

MILE MARKER, STATION OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 / 2.42	2.5 / 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (in) 3.0 lb/ft 1.3	4.0 / 1.7	4.0Mod / 1.7	FND-ATION	TUBULAR STEEL DIA (in) 3.0 lb/ft 7.6	3.5 / 9.0	4.0 / 10.8	5.0 / 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
INT #5 0.054 RAMP D RT	(W3-1 symbol)	1	36	36	9.00						2					X		2															W3-1		
0.082 RAMP D RT	EAST	1	24	12	2.00																												M3-2 GREEN ON WHITE		
	WEST	1	24	12	2.00																												M3-4 GREEN ON WHITE		
	VERMONT 64	1	24	24	4.00																												M1-5		E-136B
	VERMONT 64	1	24	24	4.00																												M1-5		E-136B
	←	1	21	15	2.19																											#2	M6-1L GREEN ON WHITE		
	↗	1	21	15	2.19																												M6-2R GREEN ON WHITE		
	TO	1	24	12	2.00																												M4-5 GREEN ON WHITE		
	TO	1	24	12	2.00																												M4-5 GREEN ON WHITE		
	VERMONT 14	1	24	24	4.00																												M1-5		E-136B
	VERMONT 12	1	24	24	4.00																												M1-5		E-136B
	←	1	21	15	2.19						2										X											#2	M6-1L GREEN ON WHITE		
	↗	1	21	15	2.19																												M6-2R GREEN ON WHITE		
0.110 RAMP D RT	← WILLIAMSTOWN 4	1	72	12	6.00																												D1-1a		E-123
	← BROOKFIELD 13	1	72	12	6.00																												D1-1a		E-123
	NORWICH UNIV. 4 ↗	1	72	12	6.00						2										X												D1-1a		E-123
	NORTHFIELD 5 ↗	1	72	12	6.00																												D1-1a		E-123
0.138 RAMP D LT	* (sign)	1	54	48	~~18.00~~																												BACK TO BACK *SIGN WAS SALAGED	145	
	WRONG WAY	1	36	24	6.00																												R5-1a		
	(R9-4a symbol)	1	24	24	4.00						2							2						X									R9-4a		
0.138 RAMP D RT	←4 GAS/DIESEL 3→	1	72	10	5.00																												VD-502G		E-133
	←4 FOOD 4→	1	72	10	5.00																												VD-502F		E-133
	WRONG WAY	1	36	24	6.00																												R5-1a BACK TO BACK		
	LODGING 5→	1	72	10	5.00																												VD-502L		E-133
	INFORMATION 4→	1	72	10	5.00																												VD-502I		E-133
	←6 CAMPING	1	72	10	5.00						2												2	X									VD-502C		E-133
0.156 RAMP D LT	(OM1-1 marker)	1	18	18	2.25						1				X			1															OM1-1		
												FT	FT	FT	FT 9.5	FT 30.9	FT		EA.	LB	LB 137.0	LB		LB 380.1	LB	LB	LB								
SUBTOTALS SHEET 49					SF ~~127.01~~ 109.01	SF	EA.	SF				FT			FT 40.4					LB 137.0			EA. 2	LB 380.1				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: ROYALTON-MIDDLESEX
PROJECT NUMBER: IMG SIGN(19)

FILE NAME:	090106_tss_int5.xls	PLOT DATE:	8/12/2009
PROJECT LEADER:	CRB	DRAWN BY:	JH
DESIGNED BY:	BDB	CHECKED BY:	DAM
TRAFFIC SIGN SUMMARY SHEET # 49		SHEET	101 OF 163