QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

		BRIDGE	ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
			10 000		10 000	LF	SHOULDER BERM REMOVAL	203.40	EST
			1		1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-
			1		1	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-
			20 000		20 000	LB	BITUMINOUS CRACK SEALING, " BLOW AND GO" METHOD (AASHTO M 324 (ASTM D 6690) TYPE II)	417.20	EST
		300			300	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	EST
		100			100	CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	EST
			450		450	HR	POWER BROOM RENTAL, TYPE I	608.30	EST
			1000		1000	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST
			500		500	HR	FLAGGERS	630.15	EST
				1	1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
			1		1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
			1		1	LS	TRAFFIC CONTROL	641.10	-
			6		6	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
			248 000		248 000	LF	6 INCH WHITE LINE	646.214	1180
			194 000		194 000	LF	6 INCH YELLOW LINE	646.215	394
			3 400		3 400	LF	12 INCH WHITE LINE	646.24	52
			100		100	LF	24 INCH STOP BAR	646.26	-
			52		52	EA	LETTER OR SYMBOL	646.30	-
			248 000		248 000	LF	TEMPORARY 6 INCH WHITE LINE, PAINT	646.622	1180
			194 000		194 000	LF	TEMPORARY 6 INCH YELLOW LINE, PAINT	646.632	397
			1700		1700	LF	TEMPORARY 12 INCH WHITE LINE, PAINT	646.662	52
			100		100	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	-
			52		52	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-
			4 700		4 700	EA	LINE STRIPING TARGETS	646.76	30
			108 500		108 500	SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	EST
			1		1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-
			30		30	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE I)	900.680	EST
			6 100		6 100	TON	SPECIAL PROVISION (MICROSURFACE TREATMENT , TYPE II)	900.680	107
			5 350		5 350	CWT	SPECIAL PROVISION (FOG SEAL SURFACE TREATMENT)	900.683	25

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		MICROSURFACE TREATMENT, TYPE II
5 853	TON	MAINLINE
32	TON	EXIT 13
76	TON	EXIT 14
32	TON	EXIT 15
107	TON	ROUNDING
6 100	TON	TOTAL
		FOG SEAL SURFACE TREATMENT
5 150	CWT	MAINLINE
45	CWT	EXIT 13
85	CWT	EXIT 14
45	CWT	EXIT 15
25	CWT	ROUNDING
5 350	CWT	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: NORWICH - FAIRLEE
PROJECT NUMBER: IM SURF (19)

FILE NAME: 09A380\p09A380.dgn
PROGRAM MANAGER : K. MARSHIA
DESIGNED BY: JLR
IPARM FILE NAME: p09A380#5.i

PLOT DATE: 23-APR-2010
DRAWN BY: JLR
CHECKED BY: PAVT MGMT
SHEET 4 OF 11