

# COMPOSITE QUANTITY SHEET # 1

				MONTPELIER IM MEMB (23)				BERLIN - WATERBURY IM SURF (20)				QUANTITIES		DESCRIPTIONS			
				BRIDGE 42N	BRIDGE 42S	ROADWAY	FULL C.E.			BRIDGE	ROADWAY	FULL C.E.	GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUND
															<b>BEGIN ITEMS COMMON TO ALL ALTERNATES</b>		
											10,000		10,000	LF	SHOULDER BERM REMOVAL	203.40	EST.
						1				1			2	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST.
				700	4,043								4,743	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	-
				16	9								25	CWT	EMULSIFIED ASPHALT	404.65	-
						1				1			2	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-
											20,000		20,000	LB	BITUMINOUS CRACK SEALING, "BLOW AND GO" METHOD	417.20	EST.
					2,820								2,820	LB	STRUCTURAL STEEL	506.60	-
				135	140								275	GAL	WATER REPELLANT, SILANE	514.10	-
				89	89					750			928	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	10
				3,159	20								3,179	SY	SHEET MEMBRANE WATERPROOFING ,TORCH APPLIED	519.20	EST.
				74	74								148	LF	JOINT SEALER, HOT POURED	524.11	-
				3,159	20								3,179	SY	REMOVAL OF BRIDGE PAVEMENT	529.10	EST.
				200	50								250	SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS I	580.10	EST.
				80	40								120	SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS II	580.11	EST.
				20	20								40	CY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS III	580.12	EST.
				28,432	180								28,612	SF	SURFACE PREPARATION FOR MEMBRANE	580.16	EST.
				20	20					100			140	SF	RAPID SETTING CONCRETE REPAIR MATERIAL W/COARSE AGGREGATE	580.20	EST.
				5	5								10	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.
											200		200	HR	POWER BROOM RENTAL, TYPE I	608.30	EST.
				5	5								10	HR	TRUCK RENTAL	608.37	EST.
				240	240								480	HR	TRUCK MOUNTED ATTENUATOR	608.45	EST.
				3	3								6	EA	ENERGY ABSORPTION ATTENUATOR	621.56	-
				1,625	1,450								3,075	LF	TEMPORARY TRAFFIC BARRIER	621.90	-
				1,500	1,450								2,950	LF	REMOVE AND RESET TEMPORARY TRAFFIC BARRIER	621.95	-
				800	800						1,000		2,600	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
											300		300	HR	FLAGGERS	630.15	EST.
							0.5				0.5		1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
						0.5					0.5		1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
											1		1	LS	TRAFFIC CONTROL (IM SURF (20))	641.10	-
				1									1	LS	TRAFFIC CONTROL (I-89 BRIDGE NO.42N)	641.10	-
					1								1	LS	TRAFFIC CONTROL (I-89 BRIDGE NO.42S)	641.10	-
				4	1						6		11	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
				1	2								3	EA	PORTABLE ARROW BOARD	641.16	-

PROJECT NAME: BERLIN - WATERBURY	MONTPELIER
PROJECT NUMBER: IM SURF (20)	IM MEMB (23)
FILE NAME: /pave/09a382/p09a382.dgn	PLOT DATE: 08-JUN-2010
PROJECT LEADER: MIKE FOWLER	DRAWN BY: WILDER
DESIGNED BY: WILDER	CHECKED BY: PAVT MGMT
IPARM FILE NAME: p09a382_03.i	SHEET 3 OF 63