

COMPOSITE QUANTITY SHEET # 2

				MONTPELIER IM MEMB (23)				BERLIN - WATERBURY IM SURF (20)				QUANTITIES		DESCRIPTIONS				
				BRIDGE 42N	BRIDGE 42S	ROADWAY	FULL C.E.			BRIDGE	ROADWAY	FULL C.E.	GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUND	
					1,450						78,750		80,200	LF	6 INCH WHITE LINE	646.214	-	
					1,160						65,500		66,660	LF	6 INCH YELLOW LINE	646.215	-	
											2,250		2,250	LF	12 INCH WHITE LINE	646.24	-	
											25		25	LF	24 INCH STOP BAR	646.26	-	
											14		14	EA	LETTER OR SYMBOL	646.30	-	
				1,380							79,250		80,630	LF	DURABLE 6 INCH WHITE LINE, POLYUREA	646.424	-	
				1,100							62,500		63,600	LF	DURABLE 6 INCH YELLOW LINE, POLYUREA	646.434	-	
											2,000		2,000	LF	DURABLE 12 INCH WHITE LINE, POLYUREA	646.464	-	
											25		25	LF	DURABLE 24 INCH STOP BAR, POLYUREA	646.484	-	
											14		14	EA	DURABLE LETTER OR SYMBOL, POLYUREA	646.494	-	
				5,150	5,250						158,000		168,400	LF	TEMPORARY 6 INCH WHITE LINE	646.620	-	
				5,150	5,250						128,000		138,400	LF	TEMPORARY 6 INCH YELLOW LINE	646.630	-	
											4,250		4,250	LF	TEMPORARY 12 INCH WHITE LINE	646.660	-	
											50		50	LF	TEMPORARY 24 INCH STOP BAR	646.680	-	
											28		28	EA	TEMPORARY LETTER OR SYMBOL	646.690	-	
				90	90						3,500		3,680	EA	LINE STRIPING TARGETS	646.76	EST.	
				1,320	780								2,100	SF	PAVEMENT MARKING MASK	646.86	EST.	
						1					1		2	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-	
						1							1	LU	SPECIAL PROVISION (INCENTIVE/DISINCENTIVE) (N.A.B.I.)	900.650	-	
				0.5	0.5								1	LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, BRIDGE DECK RESURFACING) (N.A.B.I.)	900.650	-	
				0.5	0.5								1	LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT, BRIDGE DECK RESURFACING) (N.A.B.I.)	900.650	-	
				530	330								860	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, BRIDGE DECK RESURFACING)	900.680	-	
											15		15	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE I)	900.680	EST.	
															END ITEMS COMMON TO ALL ALTERNATES			
															BEGIN ALTERNATE A			
											18,500		18,500	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	-	
											65		65	CWT	EMULSIFIED ASPHALT	404.65	-	
											71,500		71,500	SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	-	
											1		1	LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT) (N.A.B.I.)	900.650	-	
											354,000		354,000	SY	SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C)	900.675	-	
											1,000		1,000	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680	EST.	
															END ALTERNATE A			
															BEGIN ALTERNATE B			
											354,000		354,000	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	-	
											365		365	CWT	EMULSIFIED ASPHALT	404.65	-	
											31,500		31,500	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	-	
											1		1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-	
											1		1	LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32	-	
															END ALTERNATE B			
															PROJECT NAME: BERLIN - WATERBURY			
															PROJECT NUMBER: IM SURF (20)			
															FILE NAME: /pave/09a382/p09a382.dgn			
															PLOT DATE: 08-JUN-2010			
															PROJECT LEADER: MIKE FOWLER			
															DRAWN BY: WILDER			
															DESIGNED BY: WILDER			
															CHECKED BY: PAVT MGMT			
															IPARM FILE NAME: p09a382_04.i			
															SHEET 4 OF 63			