QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

		BRIDGE	ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
							BEGIN ITEMS COMMON TO ALL ALTERNATES		
			10,000		10,000	LF	SHOULDER BERM REMOVAL	203.40	EST
			1		1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST
			1		1	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-
			20,000		20,000	LB	BITUMINOUS CRACK SEALING, "BLOW AND GO" METHOD	417.20	EST
		750			750	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	10
		100			100	CF	RAPID SETTING CONCRETE REPAIR MATERIAL	580.20	EST
							WITH COURSE AGGREGATE		
			200		200	HR	POWER BROOM RENTAL, TYPE I	608.30	EST
			1,000		1,000	HR	UNIFORMED TRAFFIC OFFICERS	630.10	-
			300		300	HR	FLAGGERS	630.15	-
				0.5	0.5	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
			0.5		0.5	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
			1		1	LS	TRAFFIC CONTROL (IM SURF(20))	641.10	-
			6		6	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
			78,750		78,750	LF	6 INCH WHITE LINE	646.214	235
			65,500		65,500	LF	6 INCH YELLOW LINE	646.215	133
			2,250		2,250	LF	12 INCH WHITE LINE	646.24	89
			25		25	LF	24 INCH STOP BAR	646.26	-
			14		14	EA	LETTER OR SYMBOL	646.30	-
			79,250		79,250	LF	DURABLE 6 INCH WHITE LINE, POLYUREA	646.424	299
			62,500		62,500	LF	DURABLE 6 INCH YELLOW LINE, POLYUREA	646.434	223
			2,000		2,000	LF	DURABLE 12 INCH WHITE LINE, POLYUREA	646.464	37
			25		25	LF	DURABLE 24 INCH STOP BAR, POLYUREA	646.484	-
			14		14	EA	DURABLE LETTER OR SYMBOL, POLYUREA	646.494	-
			158,000		158,000	LF	TEMPORARY 6 INCH WHITE LINE	646.620	534
			128,000		128,000	LF	TEMPORARY 6 INCH YELLOW LINE	646.630	356
			4,250		4,250	LF	TEMPORARY 12 INCH WHITE LINE	646.660	126
			50		50	LF	TEMPORARY 24 INCH STOP BAR	646.680	-
			28		28	EA	TEMPORARY LETTER OR SYMBOL	646.690	-
			3500		3500	EA	LINE STRIPING TARGETS	646.76	366
			1		1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-
			15		15	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE	900.680	EST
							PAVEMENT SURFACE PREPARATION, TYPE I)		
							END ITEMS COMMON TO ALL ALTERNATES		

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: BERLIN - WATERBURY
PROJECT NUMBER: IM SURF (20)

FILE NAME: /pave/09a382/p09a382.dgn
PROJECT LEADER: MIKE FOWLER
DESIGNED BY: WILDER
IPARM FILE NAME: p09a382_11.i

PLOT DATE: 21-MAY-2010
DRAWN BY: WILDER
CHECKED BY: PAVT MGMT
SHEET 11 OF 63