QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

			ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
							BEGIN ALTERNATE A		
			18,500		18,500	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	177
			65		65	CWT	EMULSIFIED ASPHALT	404.65	5
			71,500		71,500	SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	375
			1		1	LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT) (N.A.B.I.)	900.650	-
			354,000		354,000	SY	SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C)	900.675	928
			1,000		1,000	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680	EST
							END ALTERNATE A		

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		ALTERNATE A
		COLD PLANING, BITUMINOUS PAVEMENT
211	SY	BEGIN PROJECT NB
211	SY	END PROJECT NB
211	SY	BEGIN PROJECT SB
211	SY	END PROJECT SB
1361	SY	BRIDGE 41N
1472	SY	BRIDGE 43N
1353	SY	BRIDGE 45N
1558	SY	BRIDGE 41S
1573	SY	BRIDGE 43S
1390	SY	BRIDGE 45S
134	SY	EXIT 8 RAMP A
134	SY	EXIT 8 RAMP B
134	SY	EXIT 8 RAMP C
134	SY	EXIT 8 RAMP D
134	SY	EXIT 9 RAMP A
134	SY	EXIT 9 RAMP B
134	SY	EXIT 9 RAMP C
134	SY	EXIT 9 RAMP D
7700	SY	SPOT REPAIR (ESTIMATED)
18,323	SY	SUBTOTAL
177	SY	ROUNDING
18,500	SY	TOTAL
		SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C)
159,573	SY	MAINLINE NB
159,397	SY	MAINLINE SB
4,077	SY	EXIT 8 RAMP "A"
2,891	SY	EXIT 8 RAMP "B"
7,176	SY	EXIT 8 RAMP "C"
6,893	SY	EXIT 8 RAMP "D"
3,704	SY	EXIT 9 RAMP "A"
2,808	SY	EXIT 9 RAMP "B"
3,035	SY	EXIT 9 RAMP "C"
3,518	SY	EXIT 9 RAMP "D"
353,072	SY	SUBTOTAL
928	SY	ROUNDING
354,000	SY	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: BERLIN - WATERBURY
PROJECT NUMBER: IM SURF (20)

FILE NAME: /pave/09a382/p09a382.dgn
PROJECT LEADER: MIKE FOWLER
DESIGNED BY: WILDER
IPARM FILE NAME: p09a382_12.i

PLOT DATE: 21-MAY-2010
DRAWN BY: HUNT
CHECKED BY: PAVT MGMT
SHEET 12 OF 63