QUANTITY SHEET 3

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

			ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
							BEGIN ALTERNATE B		
			354,000		354,000	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	928
			365		365	CWT	EMULSIFIED ASPHALT	404.65	5
			31,500		31,500	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	604
			1		1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
			1		1	LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32	-
							END ALTERNATE B		

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		ALTERNATE B
		COLD PLANING, BITUMINOUS PAVEMENT
159,573	SY	MAINLINE NB
159,397	SY	MAINLINE SB
4,077	SY	EXIT 8 RAMP "A"
2,891	SY	EXIT 8 RAMP "B"
7,176	SY	EXIT 8 RAMP "C"
6,893	SY	EXIT 8 RAMP "D"
3,704	SY	EXIT 9 RAMP "A"
2,808	SY	EXIT 9 RAMP "B"
3,035	SY	EXIT 9 RAMP "C"
3,518	SY	EXIT 9 RAMP "D"
353,072	SY	TOTAL
928	SY	ROUNDING
354,000	SY	GRAND TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
13,963	TON	MAINLINE NB
13,947	TON	MAINLINE SB
357	TON	EXIT 8 RAMP "A"
253	TON	EXIT 8 RAMP "B"
628	TON	EXIT 8 RAMP "C"
603	TON	EXIT 8 RAMP "D"
325	TON	EXIT 9 RAMP "A"
246	TON	EXIT 9 RAMP "B"
266	TON	EXIT 9 RAMP "C"
308	TON	EXIT 9 RAMP "D"
30,896	TON	TOTAL
604	TON	ROUNDING
31,500	TON	GRAND TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: BERLIN - WATERBURY
PROJECT NUMBER: IM SURF (20)

FILE NAME: /pave/09a382/p09a382.dgn
PROJECT MANAGER: MIKE FOWLER
DESIGNED BY: WILDER
IPARM FILE NAME: p09a382_13.i

PLOT DATE: 21-MAY-2010
DRAWN BY: WILDER
CHECKED BY: PAVT MGMT
SHEET 13 OF 63