

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES							TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES				
					ROADWAY	I89 - BRIDGE NO. 42N	I89 - BRIDGE NO. 42S	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
					1				1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
						700	4043		4743		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10				
						16	9		25		CWT	EMULSIFIED ASPHALT	404.65				
					1				1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
							2820		2820		LB	STRUCTURAL STEEL	506.60				
						135	140		275		GAL	WATER REPELLENT, SILANE	514.10				
						89	89		178		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10				
						3159	20		3179		SY	SHEET MEMBRANE WATERPROOFING, TORCH APPLIED	519.20	EST.*			
						74	74		148		LF	JOINT SEALER, HOT POURED	524.11				
						3159	20		3179		SY	REMOVAL OF BRIDGE PAVEMENT	529.10	EST.*			
						200	50		250		SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS I	580.10	EST.			
						80	40		120		SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS II	580.11	EST.			
						20	20		40		CY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS III	580.12	EST.			
						28432	180		28612		SF	SURFACE PREPARATION FOR MEMBRANE	580.16	EST.*			
						20	20		40		CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	EST.			
						5	5		10		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.			
						5	5		10		HR	TRUCK RENTAL	608.37	EST.			
						240	240		480		HR	TRUCK-MOUNTED ATTENUATOR	608.45	EST.			
						3	3		6		EACH	ENERGY ABSORPTION ATTENUATOR	621.56				
						1625	1450		3075		LF	TEMPORARY TRAFFIC BARRIER	621.90				
						1500	1450		2950		LF	REMOVE AND RESET TEMPORARY TRAFFIC BARRIER	621.95				
						800	800		1600		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.			
								0.5	0.5		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
					0.5				0.5		LS	MOBILIZATION/DEMOBILIZATION	635.11				
						1			1		LS	TRAFFIC CONTROL (I-89 - BRIDGE NO. 42N)	641.10				
							1		1		LS	TRAFFIC CONTROL (I-89 - BRIDGE NO. 42S)	641.10				
						4	1		5		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
						1	2		3		EACH	PORTABLE ARROW BOARD	641.16				
							1450		1450		LF	6 INCH WHITE LINE	646.214				
							1160		1160		LF	6 INCH YELLOW LINE	646.215				
						1380			1380		LF	DURABLE 6 INCH WHITE LINE, POLYUREA	646.424				
						1100			1100		LF	DURABLE 6 INCH YELLOW LINE, POLYUREA	646.434				
						5150	5250		10400		LF	TEMPORARY 6 INCH WHITE LINE	646.620				
						5150	5250		10400		LF	TEMPORARY 6 INCH YELLOW LINE	646.630				
						90	90		180		EACH	LINE STRIPING TARGETS	646.76				
						1320	780		2100		SF	PAVEMENT MARKING MASK	646.86				
					1				1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50				
					1				1		LU	SPECIAL PROVISION (NCENTIVE/DISINCENTIVE)(N.A.B.I.)	900.650				
						0.5	0.5		1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, BRIDGE DECK RESURFACING)(N.A.B.I.)	900.650				
						0.5	0.5		1		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT, BRIDGE DECK	900.650				

\*NOTE: ITEMS 519.20, 529.10, AND 580.16 ARE ESTIMATED FOR I-89 - BRIDGE NO. 42S ONLY IN THE EVENT THAT DECK REPAIRS ARE REQUIRED.



PROJECT NAME: MONTPELIER  
PROJECT NUMBER: IM MEMB(23)  
FILE NAME: ...03.quantity sheet.ptf  
PROJECT LEADER: G. BOGUE  
DESIGNED BY: G. GOYETTE  
**QUANTITY SHEET 1**

PLOT DATE: 6/8/2010  
DRAWN BY: E. ALLING  
CHECKED BY: G. GOYETTE  
SHEET 32 OF 63