STATE OF VERMONT
AGENCY OF TRANSPORTATION

TEMPORARY TRAFFIC SIGN SUMMARY SHEET 4

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	TEMP. & EXISTING SIGNS TEMP. SIGNS	EXIST. SIGNS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (In) FOUNDATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
I-89 SIGN SUMMARY – SEE TRAFFIC CONTROL SHEETS 1 & 2 FOR LOCATIONS										OPTION ITEMS																							
4 LOCATIONS	ROAD WORK AHEAD	4	48	48	16.00																										W20-1	-	SHS
4 LOCATIONS	SPEED LIMIT 50	4	48	48	16.00																										W3-5	-	SHS
4 LOCATIONS	LEFT LANE CLOSED 1/2 MILE	4	48	48	16.00																										W20-5L	-	SHS
4 LOCATIONS	RIGHT LANE CLOSED 1/2 MILE	4	48	48	16.00																										W20-5R	-	SHS
4 LOCATIONS	FINE DOUBLED FOR SPEEDING IN WORK ZONE	4	48	60	20.00																										VR355	-	SHS

THESE ARE TEMPORARY SIGNS AND ARE BEING PAID UNDER ITEM 641.10 TRAFFIC CONTROL (I-89 - BRIDGE 42N). CONTRACTOR SHALL VERIFY NUMBER AND LOCATION OF SIGNS. NO ADJUSTMENTS TO THE BID PRICE WILL BE MADE IF ADDITIONAL SIGNS ARE REQUIRED.

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

										FT	FT	FT	FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB								
TOTALS	SF 336.0	SF	EA.	SF			FT			FT						LB		EA.			LB				EA.	EA.	LB						

Stantec

PROJECT NAME: MONTPELIER
PROJECT NUMBER: IM MEMB(23)

FILE NAME: ...\Plot Files\13_TSS 4.ptf
PROJECT LEADER: G. BOGUE
DESIGNED BY: G. GOYETTE
TRAFFIC SIGN SUMMARY 4

PLOT DATE: 5/24/2010
DRAWN BY: E. ALLING
CHECKED BY: G. GOYETTE
SHEET 42 OF 63