STATE OF VERMONT
AGENCY OF TRANSPORTATION

TEMPORARY TRAFFIC SIGN SUMMARY SHEET 7

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	TEMP. & EXISTING SIGNS: TEMP. SIGNS	EXIST. SIGNS	EXIST POST: RETAIN	EXIST POST: SALVAGE	NEW SIGN POSTS: NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (In) FOUNDATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
DETOUR SIGNING – SEE RAMP CLOSURE DETAILS FOR LOCATIONS										OPTION ITEMS																								
2 LOCATIONS		2	18	24	3.00																											WI-8L	-	SHS
1 LOCATION	ROAD CLOSED	1	48	30	10.00																											RII-2	-	SHS
1 LOCATION		1	48	24	8.00																											WI-6L	-	SHS
1 LOCATION		1	36	36	9.00																											W4-2R	-	SHS
		1	36	36	9.00																											W4-1R	-	SHS
1 LOCATION		1	36	36	9.00																											W4-2R	-	SHS
		1	36	36	9.00																											W4-5	-	SHS
					TOTALS	SF 57.0	SF	EA.	SF		FT	FT	FT	FT	FT	FT	EA	LB	LB	LB	EA.	LB	LB	LB	LB	EA.	EA.	LB						

THESE ARE TEMPORARY SIGNS AND ARE BEING PAID UNDER ITEM 641.10 TRAFFIC CONTROL (I-89 - BRIDGE 42N). CONTRACTOR SHALL VERIFY NUMBER AND LOCATION OF SIGNS. NO ADJUSTMENTS TO THE BID PRICE WILL BE MADE IF ADDITIONAL SIGNS ARE REQUIRED.

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

Stantec

PROJECT NAME: MONTPELIER
PROJECT NUMBER: IM MEMB(23)

FILE NAME: ...\Plot Files\16_TSS 7.ptf
PROJECT LEADER: G. BOGUE
DESIGNED BY: G. GOYETTE
TRAFFIC SIGN SUMMARY 7

PLOT DATE: 5/24/2010
DRAWN BY: E. ALLING
CHECKED BY: G. GOYETTE
SHEET 45 OF 63