STATE OF VERMONT
AGENCY OF TRANSPORTATION

TEMPORARY TRAFFIC SIGN SUMMARY SHEET 8

DETOUR SIGNING – SEE DETOUR SHEET 3 FOR LOCATIONS

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	TEMP. & EXISTING SIGNS: TEMP. SIGNS		EXIST. SIGNS		EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS
1 LOCATION		1	36	36	9.00						
TOTALS					SF 9.0	SF	EA.	SF	(hatched)	(hatched)	

NEW SIGN POSTS

	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75, lb/ft 1.88	SQUARE STEEL (in) 2.0, lb/ft 2.42	SQUARE STEEL (in) 2.5, lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0, lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0, lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD, lb/ft 1.7	FOUNDATION	TUBULAR STEEL Ø (in) 3.0, lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5, lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0, lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0, lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED
	OPTION ITEMS																				
1 LOCATION																					
Units	FT	FT	FT	FT	FT	FT	(hatched)	EA	LB	LB	LB		LB	LB	LB	LB					
TOTALS	FT			FT					LB			EA.	LB				EA.	EA.	LB		

	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STD. SHEET NUMBER
1 LOCATION	2-147	-	SHS

THESE ARE TEMPORARY SIGNS AND ARE BEING PAID UNDER ITEM 641.10 TRAFFIC CONTROL (I-89 - BRIDGE 42N). CONTRACTOR SHALL VERIFY NUMBER AND LOCATION OF SIGNS. NO ADJUSTMENTS TO THE BID PRICE WILL BE MADE IF ADDITIONAL SIGNS ARE REQUIRED.

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

Stantec

PROJECT NAME: MONTPELIER
PROJECT NUMBER: IM MEMB(23)

FILE NAME: ...\Plot Files\17_TSS 8.ptf
PROJECT LEADER: G. BOGUE
DESIGNED BY: G. GOYETTE
TRAFFIC SIGN SUMMARY 8

PLOT DATE: 5/24/2010
DRAWN BY: E. ALLING
CHECKED BY: G. GOYETTE
SHEET 46 OF 63