

CRACK SEALING TO BE PERFORMED AT THE FOLLOWING LOCATIONS.
 LOCATION MAY BE ADJUSTED BY THE RESIDENT ENGINEER TO
 ACCOUNT FOR FIELD CONDITIONS.

ROAD	TOWN BEGINNING	MM BEGINNING	TOWN END	MM ENDING	LENGTH	LANE LENGTH	DISTRICT	ADT
I 91 (NB)	SPRINGFIELD	44.900	WEATHERSFIELD	52.000	7.100	14.200	2	7,500
I 89 (SB)	SO. BURLINGTON	87.770	COLCHESTER	91.880	4.110	8.220	5	21,750
I 89 (NB)	RICHMOND	78.990	SO. BURLINGTON	87.390	8.400	16.800	5	16,900
I 91 (SB)	GUILFORD	0.000	BRATTLEBORO	11.920	11.920	23.840	2	10,550
US 2	DANVILLE	1.786	DANVILLE	3.100	1.314	2.628	7	6,700
US 4	KILLINGTON	7.600	BRIDGEWATER	6.023	6.918	13.836	3, 4	6,600
* BRUS 4	WEST RUTLAND	0.000	WEST RUTLAND	0.425	0.850	3.400	3	15,000
** BRUS 4	WEST RUTLAND	0.425	WEST RUTLAND	0.600	0.175	0.700	3	
*** BRUS 4	WEST RUTLAND	0.000	WEST RUTLAND	0.195	0.195	0.195	3	
VT 73	ROCHESTER	0.000	ROCHESTER	8.782	8.924	17.848	4	1,025
VT 30	RUPERT	0.000	PAWLET	2.399	6.243	12.486	1	3,400
**** VT 103	CHESTER	4.270	CHESTER	7.040	2.770	5.540	2	5,000
VT 11	CHESTER	5.222	SPRINGFIELD	3.528	6.643	13.286	2	6,500
VT 14	WILLIAMSTOWN	3.800	BARRE TOWN	1.712	4.742	9.484	6	5,750
***** VT 289	ESSEX	7.860	ESSEX	11.800	3.940	7.880	5	9,300
***** VT 289	ESSEX	-	ESSEX	-	-	1.100	5	
VT 114	CANAAN	1.500	CANAAN	5.400	3.900	7.800	9	1,550
VT 2A	ESSEX	2.800	COLCHESTER	2.242	2.942	5.884	5	10,000
TOTAL (MILES)					81.086	165.127		

- * 4 LANE DIVIDED
- ** 4 LANE UNDIVIDED
- *** JUG HANDLE
- **** CRACK SEALED BEFORE
- ***** INCLUDE RAMPS
- ***** PASSING LANE

3669 I-89 SB SOUTH BURLINGTON NOT SEALED

500 GUILFORD SB PARKING AREA NOT SEALED - NO CRACKS

CRACK SEALING LOCATION DETAIL	PROJECT NAME: STATEWIDE	
	PROJECT NUMBER: STP CRAK(28)	
	FILE NAME: p09k336.dgn	PLOT DATE: 26-FEB-2010
	PROJECT LEADER: FOWLER	DRAWN BY: LOCKE
	DESIGNED BY: LOCKE	CHECKED BY: PAVT MGMT
	p09k336det.l	SHEET 5 OF 14