

QUANTITY SHEET 1

| SUMMARY OF ESTIMATED QUANTITIES | | | | | | | | | | TOTALS | | DESCRIPTIONS | | | | DETAILED SUMMARY OF QUANTITIES | | |
|---------------------------------|--|--|--|--|--|--|---------|--------|-----------------|-------------|-------|--------------|---|-------------|-------|--------------------------------|------|-------|
| | | | | | | | ROADWAY | BRIDGE | FULL C.E. ITEMS | GRAND TOTAL | FINAL | UNIT | ITEMS | ITEM NUMBER | ROUND | QUANTITIES | UNIT | ITEMS |
| | | | | | | | 1 | | | 1 | | CY | TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.) | 204.22 | | | | |
| | | | | | | | 1013 | | | 1013 | | SY | COLD PLANING, BITUMINOUS PAVEMENT | 210.10 | | | | |
| | | | | | | | 199 | | | 199 | | LF | MILLED RUMBLE STRIPS | 213.10 | | | | |
| | | | | | | | 1 | | | 1 | | LU | PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.) | 406.50 | | | | |
| | | | | | | | | 325 | | 325 | | LF | DRILLING AND GROUTING DOWELS | 507.16 | | | | |
| | | | | | | | | 21957 | | 21957 | | LB | EPOXY COATED REINFORCING STEEL | 507.17 | | | | |
| | | | | | | | | 235 | | 235 | | EACH | MECHANICAL BAR CONNECTOR (#5) (EPOXY COATED) | 507.19 | | | | |
| | | | | | | | | 1 | | 1 | | LS | SHEAR CONNECTORS (1.608 - 7/8" X 7") | 508.15 | | | | |
| | | | | | | | | 1 | | 1 | | LS | SURFACE PREPARATION, FIELD | 513.41 | | | | |
| | | | | | | | 2.5 | 7.5 | | 10 | | GAL | WATER REPELLENT, SILANE | 514.10 | | | | |
| | | | | | | | | 42 | | 42 | | LF | BRIDGE EXPANSION JOINT, ASPHALTIC PLUG | 516.10 | | | | |
| | | | | | | | | 302 | | 302 | | SY | SHEET MEMBRANE WATERPROOFING, TORCH APPLIED | 519.20 | | | | |
| | | | | | | | 83 | 42 | | 125 | | LF | JOINT SEALER, HOT Poured | 524.11 | | | | |
| | | | | | | | | 216 | | 216 | | LF | BRIDGE RAILING, GALVANIZED NETC 2 RAIL | 525.33 | | | | |
| | | | | | | | | 1 | | 1 | | EACH | PARTIAL REMOVAL OF STRUCTURE | 529.20 | | | | |
| | | | | | | | | 1 | | 1 | | CF | RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE | 580.20 | | | | |
| | | | | | | | 2 | | | 2 | | EACH | CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES | 604.40 | | | | |
| | | | | | | | 160 | | | 160 | | LF | CAST-IN-PLACE CONCRETE CURB, TYPE B | 616.28 | | | | |
| | | | | | | | | 119 | | 119 | | LF | SNOW BARRIER | 620.75 | | | | |
| | | | | | | | 429 | | | 429 | | LF | HD STEEL BEAM GUARDRAIL, GALVANIZED | 621.21 | | | | |
| | | | | | | | 2 | | | 2 | | EACH | ANCHOR FOR STEEL BEAM RAIL | 621.60 | | | | |
| | | | | | | | 4 | | | 4 | | EACH | GUARDRAIL APPROACH SECTION, GALVANIZED NETC 2 RAIL | 621.72 | | | | |
| | | | | | | | 546 | | | 546 | | LF | REMOVAL AND DISPOSAL OF GUARDRAIL | 621.80 | | | | |
| | | | | | | | 100 | | | 100 | | HR | UNFORMED TRAFFIC OFFICERS | 630.10 | | | | |
| | | | | | | | 600 | | | 600 | | HR | FLAGGERS | 630.15 | | | | |
| | | | | | | | | | 1 | 1 | | LS | TESTING EQUIPMENT, CONCRETE | 631.16 | | | | |
| | | | | | | | | | 1 | 1 | | LS | TESTING EQUIPMENT, BITUMINOUS | 631.17 | | | | |
| | | | | | | | 1 | | | 1 | | LS | MOBILIZATION/DEMobilIZATION | 635.11 | | | | |
| | | | | | | | 400 | | | 400 | | LF | 6 INCH WHITE LINE | 646.214 | | | | |
| | | | | | | | 309 | | | 309 | | LF | 6 INCH YELLOW LINE | 646.215 | | | | |
| | | | | | | | | 94 | | 94 | | CY | SPECIAL PROVISION (HIGH PERFORMANCE CONCRETE, CLASS A LOW CEMENT) | 900.608 | | | | |
| | | | | | | | 1 | | | 1 | | LS | SPECIAL PROVISION (PUBLIC PROTECTION FOR BRIDGE PROJECTS) | 900.645 | | | | |
| | | | | | | | 1 | | | 1 | | LS | SPECIAL PROVISION (TRAFFIC CONTROL, ALL-INCLUSIVE) | 900.645 | | | | |
| | | | | | | | 1 | | | 1 | | LU | SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY) (N.A.B.I.) | 900.650 | | | | |
| | | | | | | | 1 | | | 1 | | LU | SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT) (N.A.B.I.) | 900.650 | | | | |
| | | | | | | | 207 | | | 207 | | TON | SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY) | 900.680 | | | | |