QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

		BRIDGE	ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
							BEGIN ITEMS COMMON TO ALL ALTERNATES		
			34,000		34,000	LF	SHOULDER BERM REMOVAL	203.40	350
			1		1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-
			1		1	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-
		200			200	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	5
		100			100	CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	EST
			250		250	HR	POWER BROOM RENTAL, TYPE I	608.30	EST
			1000		1000	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST
			500		500	HR	FLAGGERS	630.15	EST
				1	1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
			1		1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
			1		1	LS	TRAFFIC CONTROL	641.10	-
			6		6	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
			284,000		284,000	LF	6 INCH WHITE LINE	646.214	338
			211,000		211,000	LF	6 INCH YELLOW LINE	646.215	450
			6,200		6,200	LF	12 INCH WHITE LINE	646.24	-
			70		70	LF	12 INCH YELLOW LINE	646.25	-
			40		40	LF	24 INCH STOP BAR	646.26	-
			48		48	EA	LETTER OR SYMBOL	646.30	-
			142,000		142,000	LF	TEMPORARY 6 INCH WHITE LINE, PAINT	646.622	169
			105,500		105,500	LF	TEMPORARY 6 INCH YELLOW LINE, PAINT	646.632	225
			3,100		3,100	LF	TEMPORARY 12 INCH WHITE LINE, PAINT	646.662	-
			35		35	LF	TEMPORARY 12 INCH YELLOW LINE, PAINT	646.672	-
			20		20	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	-
			24		24	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-
			5,000		5,000	EA	LINE STRIPING TARGETS	646.76	EST
			1		1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-
							END ITEMS COMMON TO ALL ALTERNATES		

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: LYNDON - BARTON
PROJECT NUMBER: IM SURF (25)

FILE NAME: 10a120\pl0a120.dgn
PROJECT LEADER: M. FOWLER
DESIGNED BY: LOCKE
IPARM FILE NAME: pl0a120qsl.i

PLOT DATE: 11-JUN-2012 11:44
DRAWN BY: LOCKE
CHECKED BY: PAVT MGMT
SHEET 6 OF 18