

BRIDGE 33S TOP OF FORM TABLES

SPAN 3																						
GIRDER NO.	POINT	CENTERLINE BEARING PIER 2	1/20 PT.	2/20 PT.	3/20 PT.	4/20 PT.	5/20 PT.	6/20 PT.	7/20 PT.	8/20 PT.	9/20 PT.	10/20 PT.	11/20 PT.	12/20 PT.	13/20 PT.	14/20 PT.	15/20 PT.	16/20 PT.	17/20 PT.	18/20 PT.	19/20 PT.	CENTERLINE BEARING PIER 3
CENTERLINE I-91 SB STATION		1923+82.50	1923+90.35	1923+98.20	1924+06.05	1924+13.90	1924+21.75	1924+29.60	1924+37.45	1924+45.30	1924+53.15	1924+61.00	1924+68.85	1924+76.70	1924+84.55	1924+92.40	1925+00.25	1925+08.10	1925+15.95	1925+23.80	1925+31.65	1925+39.50
G1-3	TOP OF PAVEMENT ELEV.	484.01	484.11	484.21	484.31	484.40	484.50	484.60	484.70	484.80	484.90	484.99	485.09	485.19	485.29	485.39	485.49	485.58	485.68	485.78	485.88	485.98
	DEFLECTION - CS	0.00	0.03	0.05	0.07	0.10	0.11	0.13	0.14	0.16	0.16	0.16	0.16	0.16	0.14	0.13	0.11	0.10	0.07	0.05	0.03	0.00
	DEFLECTION - SDL	0.00	0.00	0.00	0.00	0.00	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.00	0.00	0.00	0.00	0.00	0.00
	TOP OF FORM ELEV.	483.26	483.38	483.51	483.63	483.75	483.87	483.99	484.10	484.21	484.31	484.41	484.51	484.60	484.69	484.77	484.85	484.93	485.01	485.08	485.15	485.23
G2-3	TOP OF PAVEMENT ELEV.	484.35	484.44	484.54	484.64	484.74	484.84	484.94	485.03	485.13	485.23	485.33	485.43	485.53	485.62	485.72	485.82	485.92	486.02	486.12	486.21	486.31
	DEFLECTION - CS	0.00	0.03	0.05	0.08	0.10	0.12	0.14	0.15	0.16	0.17	0.17	0.17	0.16	0.15	0.14	0.12	0.10	0.08	0.05	0.03	0.00
	DEFLECTION - SDL	0.00	0.00	0.00	0.00	0.00	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.00	0.00	0.00	0.00	0.00	0.00
	TOP OF FORM ELEV.	483.60	483.72	483.85	483.97	484.09	484.21	484.33	484.44	484.55	484.66	484.76	484.85	484.95	485.03	485.12	485.19	485.27	485.35	485.42	485.49	485.56
G3-3	TOP OF PAVEMENT ELEV.	484.52	484.62	484.71	484.81	484.91	485.01	485.11	485.21	485.30	485.40	485.50	485.60	485.70	485.80	485.89	485.99	486.09	486.19	486.29	486.39	486.48
	DEFLECTION - CS	0.00	0.03	0.05	0.08	0.10	0.12	0.14	0.15	0.16	0.17	0.17	0.17	0.16	0.15	0.14	0.12	0.10	0.08	0.05	0.03	0.00
	DEFLECTION - SDL	0.00	0.00	0.00	0.00	0.00	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.00	0.00	0.00	0.00	0.00	0.00
	TOP OF FORM ELEV.	483.77	483.89	484.02	484.14	484.27	484.38	484.50	484.61	484.72	484.83	484.93	485.02	485.12	485.20	485.29	485.37	485.44	485.52	485.59	485.66	485.73
G4-3	TOP OF PAVEMENT ELEV.	484.47	484.56	484.66	484.76	484.86	484.96	485.06	485.15	485.25	485.35	485.45	485.55	485.65	485.74	485.84	485.94	486.04	486.14	486.24	486.33	486.43
	DEFLECTION - CS	0.00	0.03	0.05	0.08	0.10	0.12	0.14	0.15	0.16	0.17	0.17	0.17	0.16	0.15	0.14	0.12	0.10	0.08	0.05	0.03	0.00
	DEFLECTION - SDL	0.00	0.00	0.00	0.00	0.00	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.00	0.00	0.00	0.00	0.00	0.00
	TOP OF FORM ELEV.	483.72	483.84	483.97	484.09	484.21	484.33	484.45	484.56	484.67	484.78	484.88	484.97	485.07	485.15	485.24	485.31	485.39	485.47	485.54	485.61	485.68
G5-3	TOP OF PAVEMENT ELEV.	484.29	484.39	484.49	484.59	484.69	484.79	484.88	484.98	485.08	485.18	485.28	485.38	485.47	485.57	485.67	485.77	485.87	485.97	486.06	486.16	486.26
	DEFLECTION - CS	0.00	0.03	0.05	0.07	0.10	0.11	0.13	0.14	0.16	0.16	0.16	0.16	0.16	0.14	0.13	0.11	0.10	0.07	0.05	0.03	0.00
	DEFLECTION - SDL	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.00	0.00	0.00	0.00	0.00
	TOP OF FORM ELEV.	483.54	483.67	483.79	483.91	484.03	484.15	484.27	484.38	484.49	484.59	484.70	484.79	484.89	484.97	485.06	485.14	485.22	485.29	485.37	485.44	485.51

SPAN 4																						
GIRDER NO.	POINT	CENTERLINE BEARING PIER 3	1/20 PT.	2/20 PT.	3/20 PT.	4/20 PT.	5/20 PT.	6/20 PT.	7/20 PT.	8/20 PT.	9/20 PT.	10/20 PT.	11/20 PT.	12/20 PT.	13/20 PT.	14/20 PT.	15/20 PT.	16/20 PT.	17/20 PT.	18/20 PT.	19/20 PT.	CENTERLINE BEARING ABUT. 2
CENTERLINE I-91 SB STATION		1925+42.50	1925+50.35	1925+58.20	1925+66.05	1925+73.90	1925+81.75	1925+89.60	1925+97.45	1926+05.30	1926+13.15	1926+21.00	1926+28.85	1926+36.70	1926+44.55	1926+52.40	1926+60.25	1926+68.10	1926+75.95	1926+83.80	1926+91.65	1926+99.50
G1-4	TOP OF PAVEMENT ELEV.	486.01	486.11	486.21	486.31	486.41	486.51	486.60	486.70	486.80	486.90	487.00	487.10	487.19	487.29	487.39	487.49	487.59	487.69	487.78	487.88	487.98
	DEFLECTION - CS	0.00	0.03	0.06	0.09	0.12	0.14	0.16	0.18	0.19	0.20	0.20	0.20	0.19	0.18	0.16	0.14	0.12	0.09	0.06	0.03	0.00
	DEFLECTION - SDL	0.00	0.00	0.00	0.01	0.01	0.01	0.02	0.02	0.02	0.02	0.03	0.03	0.03	0.03	0.02	0.02	0.02	0.01	0.01	0.01	0.00
	TOP OF FORM ELEV.	485.26	485.40	485.53	485.66	485.79	485.91	486.03	486.15	486.27	486.37	486.48	486.57	486.66	486.75	486.83	486.90	486.97	487.04	487.10	487.17	487.23
G2-4	TOP OF PAVEMENT ELEV.	486.35	486.45	486.55	486.64	486.74	486.84	486.94	487.04	487.14	487.23	487.33	487.43	487.53	487.63	487.73	487.82	487.92	488.02	488.12	488.22	488.32
	DEFLECTION - CS	0.00	0.03	0.06	0.09	0.13	0.15	0.17	0.19	0.20	0.21	0.21	0.21	0.20	0.19	0.17	0.15	0.13	0.09	0.06	0.03	0.00
	DEFLECTION - SDL	0.00	0.00	0.00	0.01	0.01	0.01	0.02	0.02	0.02	0.02	0.03	0.03	0.03	0.02	0.02	0.02	0.02	0.01	0.01	0.01	0.00
	TOP OF FORM ELEV.	485.60	485.73	485.86	486.00	486.13	486.25	486.38	486.50	486.61	486.72	486.82	486.92	487.01	487.09	487.17	487.24	487.32	487.38	487.44	487.51	487.57
G3-4	TOP OF PAVEMENT ELEV.	486.52	486.62	486.72	486.82	486.91	487.01	487.11	487.21	487.31	487.41	487.50	487.60	487.70	487.80	487.90	488.00	488.09	488.19	488.29	488.39	488.49
	DEFLECTION - CS	0.00	0.03	0.06	0.09	0.13	0.15	0.17	0.19	0.20	0.21	0.21	0.21	0.20	0.19	0.17	0.15	0.13	0.09	0.06	0.03	0.00
	DEFLECTION - SDL	0.00	0.00	0.00	0.01	0.01	0.01	0.02	0.02	0.02	0.02	0.03	0.03	0.03	0.02	0.02	0.02	0.02	0.01	0.01	0.01	0.00
	TOP OF FORM ELEV.	485.77	485.90	486.04	486.17	486.30	486.43	486.55	486.67	486.78	486.89	486.99	487.09	487.18	487.26	487.34	487.42	487.49	487.55	487.62	487.68	487.74
G4-4	TOP OF PAVEMENT ELEV.	486.47	486.57	486.67	486.76	486.86	486.96	487.06	487.16	487.26	487.35	487.45	487.55	487.65	487.75	487.85	487.94	488.04	488.14	488.24	488.34	488.44
	DEFLECTION - CS	0.00	0.03	0.06	0.09	0.13	0.15	0.17	0.19	0.20	0.21	0.21	0.21	0.20	0.19	0.17	0.15	0.13	0.09	0.06	0.03	0.00
	DEFLECTION - SDL	0.00	0.00	0.00	0.01	0.01	0.01	0.02	0.02	0.02	0.02	0.03	0.03	0.03	0.02	0.02	0.02	0.02	0.01	0.01	0.01	0.00
	TOP OF FORM ELEV.	485.72	485.85	485.98	486.12	486.25	486.37	486.50	486.62	486.73	486.84	486.94	487.04	487.13	487.21	487.29	487.36	487.44	487.50	487.56	487.63	487.69
G5-4	TOP OF PAVEMENT ELEV.	486.30	486.40	486.49	486.59	486.69	486.79	486.89	486.99	487.08	487.18	487.28	487.38	487.48	487.58	487.67	487.77	487.87	487.97	488.07	488.17	488.26
	DEFLECTION - CS	0.00	0.03	0.06	0.09	0.12	0.14	0.16	0.18	0.19	0.20	0.20	0.20	0.19	0.18	0.16	0.14	0.12	0.09	0.06	0.03	0.00
	DEFLECTION - SDL	0.00	0.00	0.00	0.01	0.01	0.01	0.02	0.02	0.02	0.02	0.03	0.03	0.03	0.03	0.02	0.02	0.02	0.01	0.01	0.01	0.00
	TOP OF FORM ELEV.	485.55	485.68	485.81	485.94	486.07	486.19	486.32	486.43	486.55	486.65	486.76	486.85	486.95	487.03	487.11	487.18	487.26	487.32	487.39	487.45	487.51