

BRIDGE 33N TOP OF FORM TABLES

SPAN 5																						
GIRDER NO.	POINT	CENTERLINE BEARING ABUT. 3	1/20 PT.	2/20 PT.	3/20 PT.	4/20 PT.	5/20 PT.	6/20 PT.	7/20 PT.	8/20 PT.	9/20 PT.	10/20 PT.	11/20 PT.	12/20 PT.	13/20 PT.	14/20 PT.	15/20 PT.	16/20 PT.	17/20 PT.	18/20 PT.	19/20 PT.	CENTERLINE BEARING PIER 4
CENTERLINE I-91 SB STATION		2920+86.50	2920+94.35	2921+02.20	2921+10.05	2921+17.90	2921+25.75	2921+33.60	2921+41.45	2921+49.30	2921+57.15	2921+65.00	2921+72.85	2921+80.70	2921+88.55	2921+96.40	2922+04.25	2922+12.10	2922+19.95	2922+27.80	2922+35.65	2922+43.50
G6-5	TOP OF PAVEMENT ELEV.	480.50	480.60	480.69	480.79	480.89	480.99	481.09	481.19	481.28	481.38	481.48	481.58	481.68	481.78	481.88	481.97	482.07	482.17	482.27	482.37	482.47
	DEFLECTION - CS	0.00	0.03	0.06	0.09	0.12	0.14	0.16	0.18	0.19	0.20	0.20	0.20	0.19	0.18	0.16	0.14	0.12	0.09	0.06	0.03	0.00
	DEFLECTION - SDL	0.00	0.01	0.01	0.01	0.02	0.02	0.02	0.02	0.03	0.03	0.03	0.03	0.02	0.02	0.02	0.01	0.01	0.01	0.00	0.00	0.00
	TOP OF FORM ELEV.	479.75	479.88	480.01	480.15	480.28	480.40	480.52	480.64	480.75	480.86	480.96	481.05	481.14	481.22	481.31	481.38	481.45	481.52	481.58	481.65	481.72
G7-5	TOP OF PAVEMENT ELEV.	480.67	480.77	480.87	480.96	481.06	481.16	481.26	481.36	481.46	481.55	481.65	481.75	481.85	481.95	482.05	482.15	482.24	482.34	482.44	482.54	482.64
	DEFLECTION - CS	0.00	0.03	0.06	0.09	0.13	0.15	0.17	0.19	0.20	0.21	0.21	0.21	0.20	0.19	0.17	0.15	0.13	0.09	0.06	0.03	0.00
	DEFLECTION - SDL	0.00	0.01	0.01	0.01	0.02	0.02	0.02	0.02	0.03	0.03	0.03	0.02	0.02	0.02	0.02	0.01	0.01	0.01	0.00	0.00	0.00
	TOP OF FORM ELEV.	479.92	480.06	480.19	480.32	480.46	480.58	480.71	480.82	480.94	481.04	481.14	481.23	481.33	481.41	481.49	481.56	481.63	481.69	481.76	481.82	481.89
G8-5	TOP OF PAVEMENT ELEV.	480.72	480.82	480.92	481.02	481.11	481.21	481.31	481.41	481.51	481.61	481.70	481.80	481.90	482.00	482.10	482.20	482.30	482.39	482.49	482.59	482.69
	DEFLECTION - CS	0.00	0.03	0.06	0.09	0.13	0.15	0.17	0.19	0.20	0.21	0.21	0.21	0.20	0.19	0.17	0.15	0.13	0.09	0.06	0.03	0.00
	DEFLECTION - SDL	0.00	0.01	0.01	0.01	0.02	0.02	0.02	0.02	0.03	0.03	0.03	0.02	0.02	0.02	0.02	0.01	0.01	0.01	0.00	0.00	0.00
	TOP OF FORM ELEV.	479.97	480.11	480.24	480.38	480.51	480.63	480.76	480.87	480.99	481.09	481.19	481.29	481.38	481.46	481.54	481.61	481.68	481.75	481.81	481.87	481.94
G9-5	TOP OF PAVEMENT ELEV.	480.55	480.65	480.75	480.84	480.94	481.04	481.14	481.24	481.34	481.43	481.53	481.63	481.73	481.83	481.93	482.03	482.12	482.22	482.32	482.42	482.52
	DEFLECTION - CS	0.00	0.03	0.06	0.09	0.13	0.15	0.17	0.19	0.20	0.21	0.21	0.21	0.20	0.19	0.17	0.15	0.13	0.09	0.06	0.03	0.00
	DEFLECTION - SDL	0.00	0.01	0.01	0.01	0.02	0.02	0.02	0.02	0.03	0.03	0.03	0.02	0.02	0.02	0.02	0.01	0.01	0.01	0.00	0.00	0.00
	TOP OF FORM ELEV.	479.80	479.94	480.07	480.20	480.34	480.46	480.59	480.70	480.82	480.92	481.02	481.11	481.21	481.29	481.37	481.44	481.51	481.57	481.64	481.70	481.77
G10-5	TOP OF PAVEMENT ELEV.	480.21	480.31	480.41	480.51	480.61	480.71	480.80	480.90	481.00	481.10	481.20	481.30	481.39	481.49	481.59	481.69	481.79	481.89	481.99	482.08	482.18
	DEFLECTION - CS	0.00	0.03	0.06	0.09	0.12	0.14	0.16	0.18	0.19	0.20	0.20	0.20	0.19	0.18	0.16	0.14	0.12	0.09	0.06	0.03	0.00
	DEFLECTION - SDL	0.00	0.01	0.01	0.01	0.02	0.02	0.02	0.03	0.03	0.03	0.03	0.03	0.03	0.02	0.02	0.01	0.01	0.01	0.00	0.00	0.00
	TOP OF FORM ELEV.	479.46	479.60	479.73	479.86	479.99	480.12	480.24	480.36	480.47	480.57	480.68	480.77	480.86	480.94	481.02	481.09	481.17	481.23	481.30	481.37	481.43

SPAN 6																						
GIRDER NO.	POINT	CENTERLINE BEARING PIER 4	1/20 PT.	2/20 PT.	3/20 PT.	4/20 PT.	5/20 PT.	6/20 PT.	7/20 PT.	8/20 PT.	9/20 PT.	10/20 PT.	11/20 PT.	12/20 PT.	13/20 PT.	14/20 PT.	15/20 PT.	16/20 PT.	17/20 PT.	18/20 PT.	19/20 PT.	CENTERLINE BEARING PIER 5
CENTERLINE I-91 SB STATION		2922+46.50	2922+54.35	2922+62.20	2922+70.05	2922+77.90	2922+85.75	2922+93.60	2923+01.45	2923+09.30	2923+17.15	2923+25.00	2923+32.85	2923+40.70	2923+48.55	2923+56.40	2923+64.25	2923+72.10	2923+79.95	2923+87.80	2923+95.65	2924+03.50
G6-6	TOP OF PAVEMENT ELEV.	482.50	482.60	482.70	482.80	482.90	482.99	483.09	483.19	483.29	483.39	483.49	483.58	483.68	483.78	483.88	483.98	484.08	484.17	484.27	484.37	484.47
	DEFLECTION - CS	0.00	0.03	0.05	0.07	0.10	0.11	0.13	0.14	0.16	0.16	0.16	0.16	0.16	0.14	0.13	0.11	0.10	0.07	0.05	0.03	0.00
	DEFLECTION - SDL	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.00	0.00	0.00	0.00	0.00
	TOP OF FORM ELEV.	481.75	481.88	482.00	482.12	482.24	482.36	482.48	482.59	482.70	482.80	482.91	483.00	483.10	483.18	483.27	483.35	483.43	483.50	483.57	483.65	483.72
G7-6	TOP OF PAVEMENT ELEV.	482.67	482.77	482.87	482.97	483.07	483.17	483.26	483.36	483.46	483.56	483.66	483.76	483.85	483.95	484.05	484.15	484.25	484.35	484.44	484.54	484.64
	DEFLECTION - CS	0.00	0.03	0.05	0.08	0.10	0.12	0.14	0.15	0.16	0.17	0.17	0.16	0.15	0.14	0.12	0.10	0.08	0.05	0.03	0.00	
	DEFLECTION - SDL	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.00	0.00	0.00	0.00	
	TOP OF FORM ELEV.	481.92	482.05	482.18	482.30	482.42	482.54	482.66	482.77	482.88	482.98	483.09	483.18	483.28	483.36	483.45	483.53	483.60	483.68	483.75	483.82	483.89
G8-6	TOP OF PAVEMENT ELEV.	482.73	482.82	482.92	483.02	483.12	483.22	483.32	483.41	483.51	483.61	483.71	483.81	483.91	484.00	484.10	484.20	484.30	484.40	484.50	484.59	484.69
	DEFLECTION - CS	0.00	0.03	0.05	0.08	0.10	0.12	0.14	0.15	0.16	0.17	0.17	0.16	0.15	0.14	0.12	0.10	0.08	0.05	0.03	0.00	
	DEFLECTION - SDL	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.00	0.00	0.00	0.00	
	TOP OF FORM ELEV.	481.98	482.10	482.23	482.35	482.47	482.59	482.71	482.82	482.93	483.04	483.14	483.23	483.33	483.41	483.50	483.58	483.66	483.73	483.80	483.87	483.94
G9-6	TOP OF PAVEMENT ELEV.	482.55	482.65	482.75	482.85	482.95	483.05	483.14	483.24	483.34	483.44	483.54	483.64	483.73	483.83	483.93	484.03	484.13	484.23	484.32	484.42	484.52
	DEFLECTION - CS	0.00	0.03	0.05	0.08	0.10	0.12	0.14	0.15	0.16	0.17	0.17	0.16	0.15	0.14	0.12	0.10	0.08	0.05	0.03	0.00	
	DEFLECTION - SDL	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.00	0.00	0.00	0.00	0.00	
	TOP OF FORM ELEV.	481.80	481.93	482.06	482.18	482.30	482.42	482.54	482.65	482.76	482.86	482.97	483.06	483.16	483.24	483.33	483.41	483.48	483.56	483.63	483.70	483.77
G10-6	TOP OF PAVEMENT ELEV.	482.22	482.32	482.42	482.51	482.61	482.71	482.81	482.91	483.01	483.10	483.20	483.30	483.40	483.50	483.60	483.69	483.79	483.89	483.99	484.09	484.19
	DEFLECTION - CS	0.00	0.03	0.05	0.07	0.10	0.11	0.13	0.14	0.16	0.16	0.16	0.16	0.16	0.14	0.13	0.11	0.10	0.07	0.05	0.03	0.00
	DEFLECTION - SDL	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.00	0.00	0.00	0.00	
	TOP OF FORM ELEV.	481.47	481.59	481.72	481.84	481.96	482.08	482.20	482.31	482.42	482.52	482.62	482.72	482.81	482.90	482.98	483.06	483.14	483.22	483.29	483.36	483.44

NOTES: