



ITEMS USED ON THIS SHEET	
ITEM NO.	DESCRIPTION
203.16	SOLID ROCK EXCAVATION
204.25	STRUCTURE EXCAVATION
204.30	GRANULAR BACKFILL FOR STRUCTURES
490.30	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
501.33	CONCRETE, HIGH PERFORMANCE CLASS A
501.34	CONCRETE, HIGH PERFORMANCE CLASS B
507.16	DRILLING AND GROUTING DOWELS
514.10	WATER REPELLENT, SILANE
529.15	REMOVAL OF STRUCTURE
649.31	GEOTEXTILE UNDER STONE FILL
651.15	SEED
651.25	HAY MULCH
651.35	TOPSOIL

- NOTES:**
- FOR ABUTMENT 4 FOOTING REINFORCING DETAILS, SEE ABUT. 4 REINFORCEMENT - SHEET 1.
 - FOR ABUTMENT 4 STEM, SEAT AND BACKWALL REINFORCING DETAILS, SEE ABUT. 4 REINFORCEMENT - SHEET 2.
 - FOR CONSTRUCTION JOINT DETAILS, SEE ABUTMENT DETAILS - SHEET 1.
 - EMBANKMENT AREAS DISTURBED BY CONSTRUCTION SHALL BE RESTORED UPON COMPLETION OF THE WORK BY INSTALLING TOPSOIL, SEED AND HAY MULCH.

PROJECT NAME: WINDSOR
 PROJECT NUMBER: IM 091-1(64)
 FILE NAME: z10o168Abut4S.dgn
 PROJECT LEADER: J. WILSON
 DESIGNED BY: S. BOYINGTON
 ABUTMENT 4 SECTION
 PLOT DATE: 7/30/2015
 DRAWN BY: S. GUNN
 CHECKED BY: S. HALLORAN
 SHEET 127 OF 156