



	SB	NB
El. A	731.61	731.40
El. B	732.16	731.73
El. C	731.61	730.89

24" x 6" Multiple layered fabric material impregnated with neoprene, to meet ASSHO 2.10.3M. Coat surface of trough with neoprene.

NOTE: Three coats of paint shall be applied to the interior surfaces of the expansion dam prior to erection in accordance with Item 404.03.0.

NOTE: Splash RS, and the Supporting Bars shall be made of steel conforming to A.S.T.M. A-242 or A588.

NOTES: For Secs C-C & D-D see Sh. BR 210. Expansion Dam to be fabricated to follow cross slope of roadway.

CONTRACT 1  
STAGE 1 CONSTRUCTION

<b>STATE OF VERMONT</b>	
DEPARTMENT OF HIGHWAYS	
PROJECT	LYNDON - BARTON
TOWN OF	LYNDON
ROUTE NO.	I-91 Log Sta. 1297
I-91 OVER VT. 122 & RELOC. MILLER RUN	
EXPANSION DAM DETAILS	
SCALE	AS SHOWN
IN CHARGE	H.C. MARGOLIS
DRAWN BY	M. McELROY CHECKED BY J. MATEBRATH
PROJECT NO.	I-91-3110
SHEET	173 OF 455

LYNDON-IRASBURG  
IM MEMB(29)  
SHEET 24 OF 55  
BRIDGE NO. 96S  
FOR REFERENCE ONLY

REVISED - 8-70 - C.R.O. & A.G.C.  
MADE CURBS 2'-0" HELD  
FASCIA.

PREPARED BY  
BLAUVELT ENGINEERING CO.  
CONSULTING ENGINEERS  
ORLEANS, VERMONT