

# GENERAL NOTES

1. ALL MATERIALS AND CONSTRUCTION SHALL CONFORM TO THE AGENCY OF TRANSPORTATION'S STANDARD SPECIFICATIONS FOR CONSTRUCTION, DATED 2006, AND ITS LATEST REVISIONS.
2. THE ORTHOPHOTOS USED AS THE PLAN BACKGROUND WERE SUPPLIED BY THE AGENCY OF TRANSPORTATION.
3. THE CONTRACTOR SHALL TAKE ALL PRECAUTIONS NECESSARY TO PREVENT SILTATION OR POLLUTION, ESPECIALLY THE DISCHARGE OF RAW CONCRETE, INTO ANY BROOK, STREAM OR RIVER.
4. ANY CONNECTIONS THAT ARE NOT DETAILED ON THE PLANS SHALL BE DETAILED BY THE FABRICATOR AND SUBMITTED TO THE ENGINEER FOR APPROVAL.
5. ALL WELDING SHALL CONFORM TO THE PROVISIONS OF VERMONT SPECIFICATION 506.10.

GENERAL CONSTRUCTION NOTES

1. THESE PLANS ARE INTENDED TO SERVE AS A CONSTRUCTION LAYOUT. DRAWINGS SHOULD NOT BE "SCALED". IN GENERAL, THE DETAILS ARE INTENDED TO SHOW THE END RESULT OF THE DESIGN, HOWEVER MINOR MODIFICATIONS MAY BE REQUIRED TO SUIT SPECIFIC SITE CONDITIONS, OR JOB SITE DIMENSIONS. SUCH MODIFICATIONS WILL BE EITHER COMPENSATED FOR UNDER THE UNIT PRICE ARRANGEMENT, OR WILL BE SUBJECT TO DECISIONS MADE BY THE OWNER'S REPRESENTATIVE AT THE SITE.
2. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS TO THEIR SATISFACTION AND WILL NOTIFY THE VTRANS RESIDENT ENGINEER ON ANY DISCREPANCIES PRIOR TO BEGINNING THE WORK.
3. CHANGES TO, ADDITIONS OR DELETIONS OF WORK SHALL BE BROUGHT TO THE ENGINEER PRIOR TO EXECUTION. THE ENGINEER WILL MAKE A DETERMINATION REGARDING THE REQUESTS AND WILL ISSUE WRITTEN INSTRUCTION TO THE CONTRACTOR BEFORE CHANGES ARE EXECUTED.
4. ALL WORK PERFORMED, AND MATERIALS INSTALLED IN THE EXECUTION OF THE WORK SHALL BE UNDERTAKEN IN STRICT ADHERENCE TO ALL APPLICABLE CODES, STANDARDS, REGULATIONS, AND ORDINANCES OF GOVERNMENTAL AGENCIES HAVING JURISDICTION AT THE WORK SITE.
5. THE CONTRACTOR SHALL SCHEDULE THE WORK IN A MANNER SO AS TO HAVE THE LEAST DISTURBANCE ON THE EXISTING UTILITIES AT THE WORK SITE INCLUDING INTERRUPTIONS TO ELECTRIC, TELEPHONE AND OTHER COMMUNICATIONS, GAS, SEWER, WATER, AND ANY OTHER UTILITY AT THE WORK SITE.
6. THE CONTRACTOR SHALL TAKE ALL-REASONABLE MEASURES TO MINIMIZE THE NOISE LEVELS ASSOCIATED WITH THE WORK AND WILL SCHEDULE WORK SO AS TO MINIMIZE THE EFFECTS OF THE NOISE ON THE LOCAL INHABITANTS.
7. AT THE END OF EACH WORK PERIOD, THE CONTRACTOR WILL MAKE REASONABLE EFFORTS TO KEEP THE WORK AREA CLEAN AND FREE OF CONSTRUCTION DEBRIS, RUBBISH, SPOILS, TRASH, AND OTHER FOREIGN MATERIALS. ALL SUCH RUBBISH, DEBRIS AND LIKE MATERIALS SHALL BE DISPOSED OF IN ACCORDANCE WITH ALL ORDINANCES, RULES AND REGULATIONS OF THE JURISDICTIONAL AUTHORITY, INCLUDING ENVIRONMENTAL REGULATIONS.
8. THE CONTRACTOR SHALL SUPERVISE AND EXECUTE THE WORK USING THE HIGHEST QUALITY CONSTRUCTION SKILLS AND ATTENTION TO DETAIL. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR, AND HAVE CONTROL OVER THE CONSTRUCTION MEANS METHODS, TECHNOLOGIES, SEQUENCES, AND PROCEDURES.
9. NO TRENCHES SHALL REMAIN OPEN DURING NON-WORK PERIODS. ALL EXCAVATIONS SHALL BE FILLED AT THE END OF WORK SHIFT REGARDLESS OF PROGRESS OF THE WORK.
10. NO TRENCHES SHALL REMAIN OPEN DURING CONSTRUCTION PERIODS WITHOUT CONSTRUCTION FENCING AND OTHER REQUIRED WARNING DEVICES THAT MAY INCLUDE CONES, FLASHING BEACONS, AND WARNING TAPE CORDONING OFF THE CONSTRUCTION AREA.
11. IF SNOW PLOWING OPERATIONS OR WINTER MAINTENANCE IS TAKING PLACE IN THE PROJECT AREA, VTRANS DISTRICT 4 OFFICE MUST BE CONTACTED PRIOR TO THE START OF ANY CONSTRUCTION DURING THAT TIME PERIOD.

SITE WORK GENERAL NOTES

1. CALL BEFORE YOU DIG NOTIFICATIONS AND FOLLOW-UP.
2. REMOVE DEBRIS IN ACCORDANCE WITH LOCAL ORDINANCES.

CONSTRUCTION SAFETY PLAN NOTES

1. PRE-CONSTRUCTION DAILY SAFETY MEETINGS - TAILGATE SAFETY INSTRUCTION
  - a. EMPLOYEE IN CHARGE
  - b. MOVE WORK SITE DURING SHIFT

PROJECT NAME:	HARTFORD SHARON		
PROJECT NUMBER:	FITS503		
FILE NAME:	z02848471GNT.dgn	PLOT DATE:	10/1/2010
PROJECT LEADER:	J. YOUNG	DRAWN BY:	S. GUNN
DESIGNED BY:	J. WILSON	CHECKED BY:	J. YOUNG
GENERAL NOTES SHEET #1		SHEET	5 OF 70