LEGEND

- PROPOSED HANDHOLE
- PROPOSED SPLICE VAULT
- PROPOSED COMMUNICATION CONDUIT
- EXISTING LIMIT OF WETLAND
- CONSTRUCTION NOTE
- ACTION ITEM
- EXISTING MANHOLE

LAYOUT PLAN

SCALE 1" = 200'-0

200 0 200

TABULATION OF CONSTRUCTION METHODOLOGY

CAT TRACTOR PLOW:	5590'
SPIDER PLOW:	0
TRENCH AND PLACE DUCT OR CONDUIT AS NOTED ON PLAN DRAWINGS:	0
DIRECTIONAL BORE - 8" BSP CASING:	0
HANDHOLES - 2 AT EACH LOCATION:	2
DIG TEST HOLES - LOCATE FOREIGN STRUCTURES:	10
BRIDGE ATTACHMENT:	0
INSTALL CABLE MARKERS:	6
PULL FIBER OPTIC CABLE INTO DUCT:	5800'
SPLICE VAULT & HANDHOLE SETUP:	0

PROJECT NAME: HARTFORD SHARON
PROJECT NUMBER: FITS503

FILE NAME: z06e142LA4.dgn
PROJECT LEADER: J. YOUNG
DESIGNED BY: J. DURANTE
LAYOUT PLAN (SHEET 4 OF 14)

PLOT DATE: 9/15/2010
DRAWN BY: S. GUNN
CHECKED BY: J. YOUNG
SHEET 14 OF 70