



SUGGESTED WORK ZONE WARNING SIGN SPACING

ROAD TYPE	DISTANCE BETWEEN SIGNS		
	A	B	C
URBAN (LOW SPEED) 25 - 30 MPH*	100 FT.	100 FT.	100 FT.
URBAN (HIGH SPEED) 35 - 40 MPH*	350 FT.	350 FT.	350 FT.
RURAL ROADWAYS*	500 FT.	500 FT.	500 FT.
FREeways AND EXPRESSWAYS*	1,000 FT.	1,500 FT.	2,640 FT.

* SPEED CATEGORY TO BE DETERMINED BY HIGHWAY AGENCY

SIGN DISTANCES ARE BASED ON VTRANS STANDARD E-103 FOR SPEED REDUCTION.

NOTE: THESE SET-UPS ARE TYPICALS FOR BIDDING PURPOSES ONLY. ROADWAY GEOMETRY MAY REQUIRE THE SET-UPS TO BE LONGER THAN THE LENGTHS NOTED. THIS IS AT THE DISCRETION OF THE ENGINEER AND WITHOUT EXTRA COMPENSATION.

KEY

- REFL. DRUM
- d SIGN
- ▨ WORK ZONE
- ← DIRECTION OF TRAFFIC
- ☐ TYPE III PORTABLE BREAKAWAY BARRICADE
- ☒ FLASHING ARROW BOARD
- ☒ TRUCK MOUNTED ATTENUATOR (TMA)
- ☒ PCMS PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)