COMPOSITE QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

BURLINGTON - SO. BURLINGTON IM SURF (30)				SWANTON-HIGHGATE IM SURF (28)			SUMMARY OF ESTIMATED QUANTITIES				
NON-PART.	BRIDGE	ROADWAY	FULL C.E.	BRIDGE	ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
									BEGIN ITEMS COMMON TO ALTERNATES		
		9,840			13,700		23,540	LF	SHOULDER BERM REMOVAL	203.40	
		1			1		2	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	
		6,030			5,750		11,780	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	
		400			550		950	TON	AGGREGATE SHOULDERS	402.12	
		1			1		2	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	
		10,000			32,500		42,500	LB	BITUMINOUS CRACK SEALING, "BLOW AND GO" METHOD (AASHTO M324 (ASTM D 6690) TYPE II)	417.20	
	450			310			760	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	
	100			100			200	CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	
		20			70		90	HR	POWER BROOM RENTAL, TYPE I	608.30	
1							1	EA	ADJUST ELEVATION OF VALVE BOX	629.20	
		280			280		560	HR	UNIFORMED TRAFFIC OFFICERS	630.10	
		175			200		375	HR	FLAGGERS	630.15	
			0.5			0.5	1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	
		0.5			0.5		1	LS	MOBILIZATION/DEMOBILIZATION	635.11	
		1					1	LS	TRAFFIC CONTROL (IM SURF (30))	641.10	
					1		1	LS	TRAFFIC CONTROL (IM SURF (28))	641.10	
		5			4		9	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	
					1,070		1,070	LF	4 INCH YELLOW LINE	646.21	
		48,400			172,000		220,400	LF	6 INCH WHITE LINE	646.214	
		37,500			135,370		172,870	LF	6 INCH YELLOW LINE	646.215	
		4,450			4,400		8,850	LF	12 INCH WHITE LINE	646.24	
		150			115		265	LF	24 INCH STOP BAR	646.26	
		206			50		256	EA	LETTER OR SYMBOL	646.30	
		340					340	LF	CROSSWALK MARKING	646.31	
					540		540	LF	TEMPORARY 4 INCH YELLOW LINE	646.610	
		24,200			86,000		110,200	LF	TEMPORARY 6 INCH WHITE LINE	646.620	
		18,740			67,680		86,420	LF	TEMPORARY 6 INCH YELLOW LINE	646.630	
		2,220			2,210		4,430	LF	TEMPORARY 12 INCH WHITE LINE	646.660	
		75			55		130	LF	TEMPORARY 24 INCH STOP BAR	646.680	
		103			25		128	EA	TEMPORARY LETTER OR SYMBOL	646.690	
		170					170	EA	TEMPORARY CROSSWALK MARKING	646.700	
		2,200			7,900		10,100	EA	LINE STRIPING TARGETS	646.76	
		41,000			119,060		160,060	SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	
		1			1		2	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	
		1					1	EA	SPECIAL PROVISION (VIDEO VEHICLE DETECTION SYSTEM) (I-189 @ DORSET ST.)	900.620	

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS

PROJECT NAME: BURLINGTON-SO. BURLINGTON & SWANTON-HIGHGATE

PROJECT NUMBER: IM SURF (30) & IM SURF (28)

FILE NAME: 11a024/11a024.dgn
PROJECT LEADER: M. FOWLER
DESIGNED BY: PAVT MGMT
11a024compqsl.1

PLOT DATE: 12-APR-2012
DRAWN BY: PAVT MGMT
CHECKED BY: PAVT MGMT
SHEET 5 OF 49