QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

NON-PART.	BRIDGE	ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
						BEGIN ALTERNATE A		
		72,300		72,300	SY	SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C)	900.675	732
						END ALTERNATE A		
						BEGIN ALTERNATE B		
		1		1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
		4,220		4,220	TON	SPECIAL PROVISION (6.3 MM POLYMER-MODIFIED BITUMINOUS CONCRETE PAVEMENT)(SBR OR SBS POLYMER)	900.680	47
		500		500	CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT)(RS-1H OR CRS-1H)	900.683	19
						END ALTERNATE B		

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		ALTERNATE A
		SPECIAL PROVISION (PAVER-PLACED SURFACE TREATMENT, TYPE C)
21,650	SY	RAMPS
29,416	SY	I-189 EASTBOUND
20,502	SY	I-189 WESTBOUND
732	SY	ROUNDING
72,300	SY	TOTAL
		ALTERNATE B
		SPECIAL PROVISION (6.3 MM POLYMER-MODIFIED BITUMINOUS, CONCRETE PAVEMENT)(SBR OR SBS POLYMER)
1,261	TON	RAMPS
1,716	TON	I-189 EASTBOUND
1,196	TON	I-189 WESTBOUND
47	TON	ROUNDING
4,220	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: BURLINGTON-SO. BURLINGTON

PROJECT NUMBER: IM SURF (30)

FILE NAME: 11a028/11a028.dgn
PROJECT LEADER: M. FOWLER
DESIGNED BY: L. BULLOCK
11a028qs2.1

PLOT DATE: 12-APR-2012
DRAWN BY: L. BULLOCK
CHECKED BY: M. FOWLER
SHEET 15 OF 49