QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

		BRIDGE	ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
							BEGIN ALTERNATE A		
			212,500		212,500	SY	SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C)	900.675	2109
							END ALTERNATE A		
							BEGIN ALTERNATE B		
			1		1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
			12,400		12,400	TON	SPECIAL PROVISION (6.3 MM POLYMER-MODIFIED BITUMINOUS CONCRETE PAVEMENT)(SBR OR SBS POLYMER)	900.680	127
			1,430		1,430	CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT)(RS-1H OR CRS-1H)	900.683	15
							END ALTERNATE B		

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		ALTERNATE A
		SPECIAL PROVISION (PAVER-PLACED SURFACE TREATMENT, TYPE C)
8,441	SY	RAMPS
201,950	SY	I-89 NORTHBOUND
2,109	SY	ROUNDING
212,500	SY	TOTAL
		ALTERNATE B
		SPECIAL PROVISION (6.3 MM POLYMER-MODIFIED BITUMINOUS, CONCRETE PAVEMENT)(SBR OR SBS POLYMER)
492	TON	RAMPS
11,781	TON	I-89 NORTHBOUND
127	TON	ROUNDING
12,400	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: SWANTON-HIGHGATE

PROJECT NUMBER: IM SURF (28)

FILE NAME: 11a024/11a024.dgn
PROJECT LEADER: M. FOWLER
DESIGNED BY: L. BULLOCK
11a024qs2.1

PLOT DATE: 12-APR-2012
DRAWN BY: L. BULLOCK
CHECKED BY: M. FOWLER
SHEET 41 OF 49