

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
ROADWAY	BRIDGE NO. 1N	BRIDGE NO. 3N	BRIDGE NO. 5N	BRIDGE NO. 8	FULL C.E. ITEMS	BRIDGE NO. 1S	BRIDGE NO. 3S	BRIDGE NO. 5S		GRAND TOTAL	FINAL	UNT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
	3467	3283	3275			3399	3283	3275		19982		LF	TEMPORARY 6 INCH WHITE LINE, TYPE II TAPE	646.621				
	3467	3283	3275			3399	3283	3275		19982		LF	TEMPORARY 6 INCH YELLOW LINE, TYPE II TAPE	646.631				
				48						48		LF	TEMPORARY 24 INCH STOP BAR, TYPE II TAPE	646.681				
	174	165	164			170	165	164		1002		EACH	RAISED PAVEMENT MARKERS, TYPE II	646.75				
	1321	1275	1273	600		1304	1275	1273		8321		SF	PAVEMENT MARKING MASK	646.86				
1										1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50				
				1						1		EACH	SPECIAL PROVISION (TEMPORARY TRAFFIC SIGNAL SYSTEM, PORTABLE)	900.620				
	17	10	9			14	10	9		69		GAL	SPECIAL PROVISION (REPOINTING GRANITE CURB)	900.625				
				76						76		LF	SPECIAL PROVISION (REMOVE AND REPLACE COMPRESSION JOINT SEAL)	900.640				
		25	25							25		LF	SPECIAL PROVISION (REMOVE AND REPLACE EXISTING APPROACH RAILING)	900.640				
				8991						8991		SF	SPECIAL PROVISION (SURFACE PREPARATION FOR OVERLAY)	900.670				
				999						999		SY	SPECIAL PROVISION (BRIDGE DECK OVERLAY SYSTEM, POLY-CARB FLEXOGRID)	900.675				