LOCATION			DROP INLETS		CURB		GUARDRAIL														MISC.		REMARKS
			604.412		616.305	616.41	621.17	621.173	621.174	621.175	621.20	621.205	621.50	621.60	621.65	621.70	621.75	621.76	621.77	621.80	676.10	900.620	900.620	
MM	MM	POS	REHAB. DI. CB OR MH, CLASS I		BIT. CONCRETE CURB, TYPE A	REMOVAL OF EXISTING CURB	CABLE GUARDRAIL	CABLE GUARDRAIL J- BOLT, GALV	CABLE GUARDRAIL SPLICE UNIT	REPLACEMENT OF GUARDRAIL CABLE	STEEL BEAM GUARDRAIL GALV.	STEEL BEAM GUARDRAIL GALV. W/8 FEET POSTS	M.T.S. FLARED	ANCHOR FOR STEEL BEAM RAIL	ANCHOR FOR CABLE RAIL	GUARDRAIL APPROACH SECTION, GALVANIZED TYPE I	REMOVE & RESET GUARDRAIL	REPLACE GUARDRAIL POST ASSEMBLY	REPLACE GUARDRAIL BEAM UNIT	REMOVAL & DISPOSAL OF GUARDRAIL	DELIN. W/STEEL POST	SPECIAL PROV. (CAP CURB D.I.)	SPECIAL PROV. (DECOMM. CURB D.I.)	
			EACH		LF	LF	LF	EACH	EACH	LF	LF	LF	EACH	EACH	EACH	EACH	LF	EACH	EACH	LF	EACH	EACH	EACH	
SOUTHBOUND																								
128.698	137.214	LT&RT	6					65	1	1000.0								850	375			2	30	ESTIMATED QUANTITY TO BE USED AS DIRECTED BY THE ENGINEER
	BRIDGE 82S																							SEE DETAIL ON SHEET 23
128.685	128.730	RT																						RETAIN STEEL BEAM GUARDRAIL
128.730	128.737	RT																		37.5				REMOVE MELT
128.730	128.749	RT									62.5		1								1			MTS @ 128.742 TO 128.749
	BRIDGE 82S																							SEE DETAIL ON SHEET 23
128.686	128.719	LT																						RETAIN STEEL BEAM GUARDRAIL
128.719	128.726	LT																		37.5				REMOVE MELT
128.719	128.740	LT									75.0		1								1			MTS @ 128.733 TO 128.740
	BRIDGE 83S																							SEE DETAIL ON SHEET 24
128.843	128.878	LT																			1			RETAIN BOX BEAM GUARDRAIL
128.878	128.924	LT																						RETAIN BOX BEAM BRIDGE RAIL
128.924	128.950	LT																						RETAIN STEEL BEAM GUARDRAIL
128.950	128.957	LT											1							37.5	1			REMOVE MELT, MTS @ 128.950 TO 128.957
128.872	128.878	LT			33.0	33.0																		
	BRIDGE 83S																							SEE DETAIL ON SHEET 24
128.871	128.887	RT																			1			RETAIN BOX BEAM GUARDRAIL
128.887	128.935	RT																						RETAIN BOX BEAM BRIDGE RAIL
128.935	128.980	RT																						RETAIN STEEL BEAM GUARDRAIL
128.980	128.987	RT																		37.5				REMOVE MELT
128.980	128.999	RT									62.5		1								1			MTS @ 128.992 TO 128.999
128.871	128.887	RT			81.0	81.0																		
129.120	129.253	LT																			2			RETAIN STEEL BEAM GUARDRAIL - BEGINS ON EXIT 20 OFF RAMP D
129.114	129.197	RT																			2			RETAIN STEEL BEAM GUARDRAIL
	BRIDGE 84S																							SEE DETAIL ON SHEET 25
129.356	129.558	RT						200		3080.0											1			REPLACE CABLE, RETAIN POSTS
129.542	129.752	RT					1120.0								2					1112.0				RECONSTRUCTED SHOULDER - ANCHORS @ 129.542, 129.752
129.743	129.764	RT																						RETAIN ALUMINUM RAIL
129.764	129.785	RT																						RETAIN ALUMINUM BRIDGE RAIL
129.785	129.811	RT																						RETAIN ALUMINUM RAIL
129.811	129.821	RT																						RETAIN STEEL BEAM GUARDRAIL
129.821	129.828	RT																		37.5				REMOVE MELT
129.821	129.857	RT									150.0		1								1			EXTEND EXIST. RUN, MTS @ 129.850 TO 129.857
	BRIDGE 84S																							SEE DETAIL ON SHEET 25
129.742	129.763	LT																			1			RETAIN ALUMINUM RAIL
129.763	129.784	LT																						RETAIN ALUMINUM BRIDGE RAIL
129.784	129.818	LT																						RETAIN ALUMINUM RAIL
129.818	129.839	LT																		111.0				RECONSTRUCTED SHOULDER - REPLACE STEEL BEAM GUARDRAIL,
																								ATTACH TO EXIST.
129.818	129.839	LT									75.0		1								1			REMOVE MELT, MTS @ 129.832 TO 129.839
OVERPASS BRIDGE 86																								SEE DETAIL ON SHEET 26
129.932	130.182	LT																			1			RETAIN STEEL BEAM GUARDRAIL
130.182	130.189	LT																		37.5				REMOVE MELT
130.182	130.220	LT									162.5		1								1			MTS @ 130.213 TO 130.220
129.936	130.127	LT				1006.0																		REMOVE TREATED TIMBER CURB
OVERPASS BRIDGE 86																								SEE DETAIL ON SHEET 26
130.129	130.167	RT																						RETAIN STEEL BEAM GUARDRAIL
130.167	130.174	RT																		37.5				REMOVE MELT
130.167	130.195	RT									112.5		1								1			MTS @ 130.188 TO 130.195
SUBTOTAL SHEET 18			6		114.0	1120.0	1120.0	265	1	4080.0	700.0		8		2			850	375	1485.5	17	2	30	

ITEM DETAIL SUMMARY SHEET 4

PROJECT NAME: ST. JOHNSBURY-LYNDON

PROJECT NUMBER: IM 091-3(50)

FILE NAME: lla346/cos/zlla346frm.dgn
PROJECT LEADER: PTS
DESIGNED BY: NLL
IPARM FILE NAME: plla346_18

PLOT DATE: 10/17/2013
DRAWN BY: SNG
CHECKED BY: PTS
SHEET 18 OF 72