

QUANTITY SHEET 3

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
	ROADWAY 91S	TRAINING	EROSION CONTROL	BRIDGE 43S	FULL C.E. ITEMS	ROADWAY 91N	BRIDGE 43N	ROADWAY RT 5	ROADWAY COMMON	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								1		1		LS	TRAFFIC CONTROL (US RT 5)	641.10				
	2					2		2		6		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
								3750		3750		LF	DURABLE 4 INCH WHITE LINE, POLYUREA	646.404				
								4040		4040		LF	DURABLE 4 INCH YELLOW LINE, POLYUREA	646.414				
	861					654				1515		LF	DURABLE 6 INCH WHITE LINE, RECESSED POLYUREA	646.426				
	550					528				1078		LF	DURABLE 6 INCH YELLOW LINE, RECESSED POLYUREA	646.436				
								835		835		LF	DURABLE 8 INCH WHITE LINE, POLYUREA	646.444				
								500		500		LF	DURABLE 8 INCH YELLOW LINE, POLYUREA	646.454				
	50									50		LF	DURABLE 12 INCH WHITE LINE, RECESSED POLYUREA	646.466				
								60		60		LF	DURABLE 24 INCH STOP BAR, POLYUREA	646.484				
								49		49		EACH	DURABLE LETTER OR SYMBOL, POLYUREA	646.494				
	825					800				1625		SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.11				
	180					3				183		SY	GEOTEXTILE UNDER STONE FILL	649.31				
			1600							1600		SY	GEOTEXTILE FOR SILT FENCE	649.51				
			105							105		LB	SEED	651.15				
			860							860		LB	FERTILIZER	651.18				
			4							4		TON	AGRICULTURAL LIMESTONE	651.20				
			4							4		TON	HAY MULCH	651.25				
			930							930		CY	TOPSOIL	651.35				
			1							1		LS	EPSC PLAN	652.10				
			200							200		HR	MONITORING EPSC PLAN	652.20				
			1							1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
			1425							1425		SY	TEMPORARY EROSION MATTING	653.20				
			20							20		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25				
			200							200		CY	VEHICLE TRACKING PAD	653.35				
			11							11		EACH	INLET PROTECTION DEVICE, TYPE I	653.40				
			3925							3925		LF	BARRIER FENCE	653.50				
	4.66					4.66		68.63		77.95		SF	TRAFFIC SIGNS, TYPE A	675.20				
	24					24		135		183		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
	6					3		25		34		EACH	REMOVING SIGNS	675.50				
								8		8		EACH	ERECTING SALVAGED SIGNS	675.60				
						2				2		EACH	DELINEATOR WITH STEEL POST (BLUE)	676.10				
	1					1				2		EACH	DELINEATOR WITH STEEL POST (GREEN)	676.10				
	2					2				4		EACH	DELINEATOR WITH STEEL POST (YELLOW)	676.10				
	2					3		6		11		EACH	REMOVAL OF EXISTING DELINEATOR	676.12				
								1		1		EACH	REMOVE AND RESET OVERHEAD TRAFFIC SIGN SUPPORT	677.25				
								2		2		EACH	TEMPORARY TRAFFIC SIGNAL SYSTEM	678.40				
								1		1		EACH	REMOVING AND RESETTING LIGHT POLE	679.25				
									1	1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50				
				2					2	4		CY	SPECIAL PROVISION (HIGH PERFORMANCE CONCRETE, RAPID SET)(FPQ)	900.608				

PROJECT NAME: HARTFORD
PROJECT NUMBER: IM 09I-2(79)

FILE NAME: s12a132qs.dgn
PROJECT LEADER: K. HIGGINS
DESIGNED BY: W. LAMMER
QUANTITY SHEET 3

PLOT DATE: 15-DEC-2014
DRAWN BY: K. FRIEDLAND
CHECKED BY: J. SALVATORI
SHEET 9 OF 166