



**NOTES:**

- 1) LOCATIONS OF EXISTING UTILITIES ARE APPROXIMATE.
- 2) ALL UTILITY WORK TO BE COMPLETED BY OTHERS.
- 3) THE EXISTING FIBER OPTIC ON THE SOUTHERN SIDE OF US5 WILL BE ABANDONED. IT WILL BE RE-ROUTED OUTSIDE THE PROJECTS LIMITS VIA OVERHEAD LINE BY FALL 2014.
- 4) VALVES SHALL BE INSTALLED ON THE EXISTING 12" WATER LINE AS SHOWN ON THE PLANS BY FALL 2014. PRIOR TO CONSTRUCTION, THE VALVES WILL BE CLOSED AND THE LINE BETWEEN THE LINES SHALL BE ABANDONED.
- 5) THE NEW 12" WATER LINE SHALL NOT BE INSTALLED UNTIL AFTER THE PIER #1 IS REMOVED.
- 6) NO DRILLING OR BLASTING SHALL OCCUR WITHIN 10 FEET OF ANY UTILITY WITHOUT THE WRITTEN PERMISSION OF THE UTILITY OWNER. SEE SPECIAL PROVISIONS FOR FURTHER DETAILS.

EXISTING 8" D.I. WATER LINE

EXISTING 12" D.I. WATER LINE (TO BE ABANDONED)

INSTALL SHUT OFF VALVE STA 354+75.00, OFFSET 50.0' RT

EXISTING FIBER OPTIC (CAPPED WITH CONCRETE)

**UTILITY LAYOUT SHEET**

SCALE 1" = 20' - 0"  
 20 0 20

PROJECT NAME: HARTFORD	PLOT DATE: 15-DEC-2014
PROJECT NUMBER: IM 091-2(79)	DRAWN BY: K. FRIEDLAND
FILE NAME: s12a132bdr_util.dgn	CHECKED BY: J. SALVATORI
DESIGNED BY: W. LAMMER	SHEET 56 OF 166
UTILITY LAYOUT SHEET	