



	STEEL	WOOD
SECTION	W6x9	6"x8"
OFFSET BLOCK	6"x8" WOOD	6"x8" RECESSED WOOD
EMBEDMENT DEPTH	POST# 1-6	7'-0"
	POST# 7&8	6'-0"
	POST# 9	SEE STD. G-1

POST TABLE

NOTES:

1. THRIE-BEAM TERMINAL CONNECTOR SHALL BE INCLUDED IN THE UNIT BID PRICE FOR GUARDRAIL APPROACH SECTION TO CONCRETE BRIDGE RAILING, TL-3.
2. UNLESS OTHERWISE DIRECTED BY THE ENGINEER, A COMPOSITE MATERIAL OFFSET BLOCK FROM THE APPROVED PRODUCTS LIST MAY BE SUBSTITUTED FOR A OFFSET BLOCK OF SIMILAR DIMENSIONS.
3. THIS APPROACH RAILING MEETS THE REQUIREMENTS FOR A NCHRP REPORT 350 TL-3 SERVICE LEVEL.
4. SEE STANDARDS C-10, G-1 AND S-363.

PROJECT NAME: HARTFORD
PROJECT NUMBER: IM 091-2(79)

FILE NAME: s12a132rail_details.dgn PLOT DATE: 15-DEC-2014
PROJECT LEADER: K. HIGGINS DRAWN BY: C. MOONEY
DESIGNED BY: C. MOONEY CHECKED BY: W. LAMMER
APPROACH RAIL DETAILS SHEET 68 OF 166