QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

BRIDGE	ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
	1300		1300	CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT) (RS-1H OR CRS-1H)	900.683	EST
					END ITEMS COMMON TO ALL ALTERNATES		
					BEGIN ALTERNATE A		
	547 000		547 000	SY	SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C)	900.675	5490
					END ALTERNATE A		
					BEGIN ALTERNATE B		
	1		1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
	31 000		31 000	TON	SPECIAL PROVISION (6.3 MM POLYMER MODIFIED BITUMINOUS CONCRETE PAVEMENT) (SBR OR SBS POLYMER)	900.680	501
	3 750		3 750	CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT) (RS-1H OR CRS-1H)	900.683	EST
					END ALTERNATE B		

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		ALTERNATE A
		SPECIAL PROVISION (PAVER-PLACED SURFACE TREATMENT, TYPE C)
255 834	SY	MAINLINE (NB)
255 916	SY	MAINLINE (SB)
29 760	SY	INTERCHANGES
541 510	SY	SUBTOTAL
5490	SY	ROUNDING
547 000	SY	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		ALTERNATE B
		SPECIAL PROVISION (6.3 MM POLYMER MODIFIED BITUMINOUS CONCRETE PAVEMENT) (SBR OR SBS POLYMER)
14 924	TON	MAINLINE (NB)
14 928	TON	MAINLINE (SB)
647	TON	INTERCHANGES
30 499	TON	SUBTOTAL
501	TON	ROUNDING
31 000	TON	TOTAL

PROJECT NAME: WATERBURY-RICHMOND
PROJECT NUMBER: IM SURF (33)

FILE NAME: 12A178•A178.dgn
PROJECT LEADER: FOWLER
DESIGNED BY: PVT. MGT.
IPARM FILE NAME: 12A178_06.i

PLOT DATE: 10-APR-2014 14:16
DRAWN BY: PVT. MGT.
CHECKED BY: PAVT MGMT
SHEET 6 OF 19