

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
					ROADWAY	BRIDGE 97N	BRIDGE 97S	BRIDGE 98N	BRIDGE 98S	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						1					1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
						468	654	468			1590		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10				
						200	200	200			600		LF	MILLED RUMBLE STRIPS	213.10				
						12	17	12			41		CWT	EMULSIFIED ASPHALT	404.65				
					1						1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
						250	250	500			1000		LB	REINFORCING STEEL, LEVEL I	507.11				
						10	10	10			30		LF	DRILLING AND GROUTING DOWELS	507.16				
						10	10	30			50		EACH	MECHANICAL BAR CONNECTOR	507.19				
						50	50	50	50		200		GAL	WATER REPELLENT, SILANE	514.10				
						120	168	120			408		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10				
						510	710	540			1760		SY	SHEET MEMBRANE WATERPROOFING, TORCH APPLIED	519.20				
														BEGIN OPTION AA					
						60	84	60			204		LF	JOINT SEALER, HOT POURED	524.11				
						60	84	60			204		LF	JOINT SEALER, COLD POURED	524.13				
														END OPTION AA					
						510	710	540			1760		SY	REMOVAL OF BRIDGE PAVEMENT	529.10				
						51	71	54			176		SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS I	580.10				
						152	213	162			527		SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS II	580.11				
						3	3	3			9		CY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS III	580.12				
						15	20	14	14		63		SY	REPAIR OF CONCRETE SUBSTRUCTURE SURFACE, CLASS I	580.13				
						5	7	5	5		22		SY	REPAIR OF CONCRETE SUBSTRUCTURE SURFACE, CLASS II	580.14				
						510	710	540			1760		SF	SURFACE PREPARATION FOR MEMBRANE	580.16				
						2	2	2	2		8		GAL	REPOINTING GRANITE BRIDGE CURB	616.225				
						250	250	250	250		1000		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
						100	100	400	400		1000		HR	FLAGGERS	630.15				
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
					1						1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
						588	588	603			1779		LF	6 INCH WHITE LINE	646.214				
						292	292	302			886		LF	6 INCH YELLOW LINE	646.215				
								126	126		252		LF	SPECIAL PROVISION (FIBER REINFORCED POLYMER (FRP), SAFSTRIP)	900.640				
						1					1		LS	SPECIAL PROVISION (PUBLIC PROTECTION FOR BRIDGE PROJECTS)(I-89 BRIDGE NO. 97N)	900.645				
							1				1		LS	SPECIAL PROVISION (PUBLIC PROTECTION FOR BRIDGE PROJECTS)(I-89 BRIDGE NO. 97S)	900.645				
								1			1		LS	SPECIAL PROVISION (PUBLIC PROTECTION FOR BRIDGE PROJECTS)(I-89 BRIDGE NO. 98N)	900.645				
									1		1		LS	SPECIAL PROVISION (PUBLIC PROTECTION FOR BRIDGE PROJECTS)(I-89 BRIDGE NO. 98S)	900.645				
									1		1		LS	SPECIAL PROVISION (TRAFFIC CONTROL ALL-INCLUSIVE TRAFFIC)(I-89 BRIDGE NO. 98S)	900.645				

PROJECT NAME: SWANTON
PROJECT NUMBER: IM 089-3(70)

FILE NAME: sl2a276qs.dgn
PROJECT LEADER: C. CARLSON
DESIGNED BY: H. SALLS
QUANTITY SHEET 1

PLOT DATE: 11-APR-2013
DRAWN BY: R. PELLETT
CHECKED BY: H. SALLS
SHEET 3 OF 31