

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES								
	BRIDGE	ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
						BEGIN OPTION EE		
		82		82	EA	DURABLE LETTER OR SYMBOL, EPOXY PAINT	646.493	-
		82		82	EA	DURABLE LETTER OR SYMBOL, POLYUREA	646.494	-
						END OPTION EE		
		290,750		290,750	LF	TEMPORARY 6 INCH WHITE LINE, PAINT	646.622	180
		229,800		229,800	LF	TEMPORARY 6 INCH YELLOW LINE, PAINT	646.632	28
		7,350		7,350	LF	TEMPORARY 12 INCH WHITE LINE, PAINT	646.662	66
		205		205	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	-
		82		82	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-
		16,500		16,500	EA	LINE STRIPING TARGETS	646.76	EST
		349,000		349,000	SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	EST
		I		I	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-
		100		100	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE I)	900.680	EST
						END ITEMS COMMON TO ALL ALTERNATES		
						BEGIN ALTERNATE A		
		725,000		725,000	SY	SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C)	900.675	1,135
						END ALTERNATE A		
						BEGIN ALTERNATE B		
		I		I	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
		42,650		42,650	TON	SPECIAL PROVISION (6.3 MM POLYMER MODIFIED BITUMINOUS CONCRETE PAVEMENT)(SBR OR SBS POLYMER)	900.680	423
		5,000		5,000	CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT)(RS-IH OR CRS-IH)	900.683	136
						END ALTERNATE B		

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS
		ALTERNATE A
		SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C)
289,798	SY	MAINLINE NORTHBOUND
374,113	SY	MAINLINE SOUTHBOUND
1,056	SY	BRIDGE 20 N & APPROACHES
1,056	SY	BRIDGE 20 S & APPROACHES
2,470	SY	BRIDGE 21S & APPROACHES
929	SY	BRIDGE 22 S & APPROACHES
1,470	SY	BRIDGE 23 S & APPROACHES
3,897	SY	BRIDGE 24 S & APPROACHES
11,517	SY	EXIT 4 RAMPS
16,825	SY	EXIT 5 RAMPS
9,387	SY	EXIT 6 RAMPS
3,191	SY	NORTHBOUND PARKING AREA (MM 20.438)
3,049	SY	NORTHBOUND PARKING AREA (MM 23.211)
2,045	SY	SOUTHBOUND PARKING AREA (MM 23.798)
3,062	SY	SOUTHBOUND WEIGH STATION (MM 21.957)
1,135	SY	ROUNDING
725,000	SY	TOTAL

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS
		ALTERNATE B
		SPECIAL PROVISION (6.3 MM POLYMER MODIFIED BITUMINOUS CONCRETE PAVEMENT)(SBR OR SBS POLYMER)
16,905	TON	MAINLINE NORTHBOUND
21,823	TON	MAINLINE SOUTHBOUND
62	TON	BRIDGE 20 N & APPROACHES
62	TON	BRIDGE 20 S & APPROACHES
144	TON	BRIDGE 21S & APPROACHES
54	TON	BRIDGE 22 S & APPROACHES
86	TON	BRIDGE 23 S & APPROACHES
227	TON	BRIDGE 24 S & APPROACHES
672	TON	EXIT 4 RAMPS
982	TON	EXIT 5 RAMPS
548	TON	EXIT 6 RAMPS
186	TON	NORTHBOUND PARKING AREA (MM 20.438)
178	TON	NORTHBOUND PARKING AREA (MM 23.211)
119	TON	SOUTHBOUND PARKING AREA (MM 23.798)
179	TON	SOUTHBOUND WEIGH STATION (MM 21.957)
423	TON	ROUNDING
42,650	TON	TOTAL

PROJECT NAME: BRATTLEBORO - ROCKINGHAM  
 PROJECT NUMBER: IM SURF (37)

FILE NAME: I2a398\pl2a398.dgn  
 PROJECT LEADER: M. FOWLER  
 DESIGNED BY: LOCKE  
 IPARM FILE NAME: pl2a398qs2.i

PLOT DATE: 27-MAR-2014 13:15  
 DRAWN BY: LOCKE  
 CHECKED BY: HARRINGTON  
 SHEET 11 OF 36