STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

SHSM = FHWA 2004 STANDARD HIIGHWAY SIGNS AND MARKINGS BOOK AND THE 2012 SUPPLEMENT TO THE 2004 EDITION

MILE MARKER, DIRECTION	SIGN LEGEND	SIGN DIMENSIONS EA.	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (in) 3.0 lb/ft 1.3	4.0 1.7	4.0Mod 1.7	TUBULAR STEEL DIA (in) FND-ATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL SHSM	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
NORTHBOUND 0.000 - 36.000 NB	BRIDGE XX I-91	24	6	10	10.08						24				X			24															NOT SHOWN ON LAYOUTS See location chart on sign detail sheet 16		149	
0.000 - 36.000 NB	RAMPX 0.000 000.00	20	6	8	6.60						20				X			20															NOT SHOWN ON LAYOUTS See location chart on sign detail sheet 16		149	
0.001 NB MED		1	36	36	9.00						2					X		2																R3-4		
0.019 NB	Welcome To VERMONT	1	60	48	20.00																														134	
	WELCOME CENTER 5 MILES	1	60	48	20.00						2												2			380.2								134	
0.099 NB MED		1	36	36	9.00						2					X		2																R3-4		
0.167 NB	RAMP 25 MPH	1	48	60	20.00						2												2	220.4										W13-3		
0.234 NB		1	18	18	2.25						1				X			1																OM1-1		
0.281 NB		1	48	48	16.00						2												2	205.2										W4-1R		
0.310 NB		1	30	30	6.25						2					X		2																R3-2		
0.317 NB MED	ONE WAY	1	54	18	6.75						2					X		2																R6-1R		
0.376 NB	SPEED LIMIT 65	1	48	60	20.00																													R2-1		
	MINIMUM 40	1	48	48	16.00						2												2			315.0										E-142
0.471 NB	NORTH	1	~~36~~ 30	~~18~~ 21	~~4.50~~ 4.38																												(INTERSTATE) WHITE ON BLUE	M3-1		
	INTERSTATE 91	1	36	36	9.00																													M1-1		
	PROJECT NATIONAL SYSTEM	1	36	36	9.00						1												1			144.0								M1-10		
												FT	FT	FT	FT 599.1	FT 110.3	FT		EA.	LB	LB	LB		LB 425.6	LB 459.0	LB 380.2	LB									
	SUBTOTALS SHEET 1	SF 184.31	SF	EA.	SF						FT				FT 709.4					LB			EA. 9	LB 1264.8				EA.	EA.	LB						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: **GUILFORD-ROCKINGHAM**
PROJECT NUMBER: **IMG SIGN(44)**

FILE NAME: z12A528tssml.xlsb
PROJECT LEADER: C. GREGORY
DESIGNED BY: J. SMITH
TRAFFIC SIGN SUMMARY SHEET 1

PLOT DATE: 4/16/2014
DRAWN BY: J. SMITH
CHECKED BY: D. MUNRO
SHEET 58 OF 157