STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

SHSM = FHWA 2004 STANDARD HIGHWAY SIGNS AND MARKINGS BOOK AND THE 2012 SUPPLEMENT TO THE 2004 EDITION

MILE MARKER, DIRECTION	SIGN LEGEND	SIGN DIMENSIONS EA.	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (in) 3.0 lb/ft 1.3	4.0 1.7	4.0Mod 1.7	TUBULAR STEEL DIA (in) FND-ATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL SHSM	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
0.688 NB	SAFETY BELTS REQUIRED	1	72	72		36.00					2												2			375.9									134	
0.783 NB		1	36	36	9.00																														134	
	STRICTLY ENFORCED	1	36	24	6.00						2					X		2																	134	
0.926 NB	STATE LAW MOVE OVER OR SLOW DOWN FOR STOPPED EMERGENCY VEHICLES	1	132	66		60.50					2												2			289.5							THINNING & TRIMMING		135	
1.021 NB	KEEP RIGHT EXCEPT TO PASS	1	48	60	20.00						2												2	206.8										146	
1.021 NB MED	KEEP RIGHT EXCEPT TO PASS	1	48	60	20.00						2												2	206.8										146	
1.940 NB MED		1	36	36	9.00						2					X		2																R3-4		
2.084 NB	511 TRAVEL INFO	1	48	48	16.00						2												2	205.2										134	
2.340 NB	ENTERING TOWN OF VERNON	1	36	24	6.00						2					X		2																		E-131
2.388 NB	MOOSE	1	48	48	16.00																														146	
	STAY ALERT	1	30	24	5.00						2												2	205.2										146	
4.178 NB MED		1	36	36	9.00						2					X		2																R3-4		
4.670 NB	REST AREA VERMONT WELCOME CENTER 1 MILE	1	186	108		139.50																											THINNING & TRIMMING		135	
	NEXT FACILITY 95 MILES	1	114	36		28.50					2																	2		1186	W10X26		Fuse-Plate Bolt Tension 28 kips Special Provision Footing (2); See Sht 3		135	
5.079 NB	ENTERING TOWN OF GUILFORD	1	36	24	6.00						2					X		2																		E-131
2.680 NB	BRIDGE PLAQUE						I																													
												FT	FT	FT	FT	FT 164.7	FT	EA.		LB	LB	LB		LB 824.0	LB	LB 665.4	LB								
SUBTOTALS SHEET 2		SF 122.00	SF 264.50	EA.	SF							FT			FT 164.7					LB			EA. 12	LB 1489.4				EA. 2	EA.	LB 1186					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: **GUILFORD-ROCKINGHAM**
PROJECT NUMBER: **IMG SIGN(44)**

FILE NAME: **z12A528tssml.xlsb** PLOT DATE: **4/15/2014**
PROJECT LEADER: **C. GREGORY** DRAWN BY: **J. SMITH**
DESIGNED BY: **J. SMITH** CHECKED BY: **D. MUNRO**
TRAFFIC SIGN SUMMARY SHEET 2 SHEET **59** OF **157**