STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 11

SHSM = FHWA 2004 STANDARD HIIGHWAY SIGNS AND MARKINGS BOOK AND THE 2012 SUPPLEMENT TO THE 2004 EDITION

MILE MARKER, DIRECTION	SIGN LEGEND	SIGN DIMENSIONS EA.	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (in) 3.0 lb/ft 1.3	4.0 1.7	4.0Mod 1.7	TUBULAR STEEL DIA (in) FND-ATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL SHSM	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
19.170 NB	KEEP RIGHT EXCEPT TO PASS	1	48	60	20.00						2												2	220.4											146	
19.170 NB MED	KEEP RIGHT EXCEPT TO PASS	1	48	60	20.00						2												2	220.4											146	
19.360 NB	WEIGH STATION 1 MILE	1	96	72		48.00					2												2			358.6									141	
19.480 NB	BRIDGE ICES BEFORE ROAD	1	48	48	16.00						2												2	205.2											W8-13	
19.645 NB MED		1	12	36	3.00						1					X		1																	OM-3L	
19.655 NB		1	12	36	3.00						1					X		1																	OM-3R	
19.820 NB	ALL TRUCKS NEXT RIGHT	1	114	48		38.00					2												2		235.8									THINNING & TRIMMING		141	
20.122 NB	WEIGH STATION NEXT RIGHT OPEN CLOSED	1	108	90		67.50					2												2				476.0								141	
20.274 NB	RAMP 30 MPH	1	48	60	20.00						2												2	206.8									THINNING & TRIMMING		W13-3	
20.400 NB		1	18	18	2.25						1				X			1																	OM1-1	
20.402 NB	WEIGH STATION	1	84	78		45.50					2												2		243.0											141	
20.447 NB		1	48	48	16.00						2												2	205.2											W4-1R	
20.513 NB MED	ONE WAY	1	54	18	6.75						2					X		2																	R6-1R	
20.640 NB MED		1	36	36	9.00						2					X		2																	R3-4	
21.124 NB	BRIDGE ICES BEFORE ROAD	1	48	48	16.00						2												2	205.2											W8-13	
21.271 NB		1	12	36	3.00						1					X		1																	OM-3R	
												FT	FT	FT	FT 9.5	FT 100.7	FT	EA.		LB	LB	LB		LB 1263.2	LB 478.8	LB 358.6	LB 476.0									
SUBTOTALS SHEET 11		SF 135.00	SF 199.00	EA.	SF			FT				FT 110.2						LB		EA. 20	LB 2576.6					EA.	EA.	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: **GUILFORD-ROCKINGHAM**
PROJECT NUMBER: **IMG SIGN(44)**

FILE NAME: **z12A528tssml.xlsb** PLOT DATE: **4/16/2014**
PROJECT LEADER: **C. GREGORY** DRAWN BY: **J. SMITH**
DESIGNED BY: **J. SMITH** CHECKED BY: **D. MUNRO**
TRAFFIC SIGN SUMMARY SHEET 11 SHEET **68** OF **157**