STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 14

SHSM = FHWA 2004 STANDARD HIIGHWAY SIGNS AND MARKINGS BOOK AND THE 2012 SUPPLEMENT TO THE 2004 EDITION

MILE MARKER, DIRECTION	SIGN LEGEND	SIGN DIMENSIONS EA.	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (in) 3.0 lb/ft 1.3	4.0 1.7	4.0Mod 1.7	TUBULAR STEEL DIA (in) FND-ATION	3.0 lb/ft 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL SHSM	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
29.218 NB	NORTH	1	~~30~~ 36	~~21~~ 18	~~4.38~~ 4.50																												(INTERSTATE) WHITE ON BLUE	M3-1		
	INTERSTATE 91	1	36	36	9.00																													M1-1		
	VERMONT NEW HAMPSHIRE 91	1	36	36	9.00						1												1		144.0								M1-10		
29.313 NB	SPEED LIMIT 65	1	48	60	20.00																												R2-1		
	MINIMUM 40	1	48	48	16.00						2												2		315.0										E-142
29.523 NB	Rockingham 7 White River Jct 42	1	150	36		37.50					2												2		265.5								THINNING AND TRIMMING		142	
29.854 NB	KEEP RIGHT EXCEPT TO PASS	1	48	60	20.00						2												2	220.4										146	
29.854 NB MED	KEEP RIGHT EXCEPT TO PASS	1	48	60	20.00						2												2	220.4										146	
30.688 NB MED		1	36	36	9.00						2					X		2															R3-4		
30.730 NB MED		1	36	36	9.00						2					X		2															R3-4		
30.785 NB	BRIDGE ICES BEFORE ROAD	1	48	48	16.00						2												2	205.2									W8-13		
30.985 NB MED	Saxtons River	1	48	28	9.33						2					X		2																147	
30.990 NB		1	12	36	3.00						1					X		1															OM-3R		
30.997 NB MED		1	12	36	3.00						1					X		1															OM-3L		
31.190 NB	ENTERING TOWN OF ROCKINGHAM	1	36	24	6.00						2					X		2																	E-131
											FT	FT	FT		FT	153.3	FT		EA.	LB	LB	LB		LB 646.0	LB 724.5	LB	LB									
SUBTOTALS SHEET 14		SF	153.71		SF	37.50	EA.		SF		FT				FT	153.3				LB			EA.	11	LB	1370.5		EA.		EA.		LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: **GUILFORD-ROCKINGHAM**
PROJECT NUMBER: **IMG SIGN(44)**

FILE NAME: **z12A528tssml.xlsb** PLOT DATE: **4/16/2014**
PROJECT LEADER: **C. GREGORY** DRAWN BY: **J. SMITH**
DESIGNED BY: **J. SMITH** CHECKED BY: **D. MUNRO**
TRAFFIC SIGN SUMMARY SHEET 14 SHEET **71** OF **157**