STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 19

SHSM = FHWA 2004 STANDARD HIIGHWAY SIGNS AND MARKINGS BOOK AND THE 2012 SUPPLEMENT TO THE 2004 EDITION

MILE MARKER, DIRECTION	SIGN LEGEND	SIGN DIMENSIONS EA.	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (in) 3.0 lb/ft 1.3	4.0 1.7	4.0Mod 1.7	TUBULAR STEEL DIA (in) FND-ATION	3.0 lb/ft 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL SHSM	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
35.180 SB		1	18	18	2.25						1				X			1																OM1-1		
35.176 SB	EXIT 6	1	78	60		32.50					2												2	182.4									E5-1a		
35.122 SB		1	48	48	16.00						2												2	205.2									W4-1R		
35.102 SB MED	ONE WAY	1	54	18	6.75						2					X		2															R6-1R		
35.061 SB		1	48	48	16.00						2												2	205.2								THINNING & TRIMMING VW-285		146	
34.770 SB	EMERGENCY STOPPING ONLY	1	48	36	12.00						2												2	190.0									R8-7		
34.675 SB	SOUTH	1	36	18	4.50																											(INTERSTATE) WHITE ON BLUE	M3-3		
	INTERSTATE 91	1	36	36	9.00																												M1-1		
	VERMONT	1	36	36	9.00						1												1		144.0								M1-10		
34.580 SB	SPEED LIMIT 65	1	48	60	20.00																												R2-1		
	MINIMUM 40	1	48	48	16.00						2												2		315.0										E-142
34.578 SB MED		1	36	36	9.00						2					X		2															R3-4		
34.390 SB	Westminster 8 Brattleboro 27	1	126	36		31.50					2												2	199.9								THINNING AND TRIMMING		145	
33.940 ~~34.200~~ SB	KEEP RIGHT EXCEPT TO PASS	1	48	60	20.00						2												2	220.4										146	
33.940 ~~34.200~~ SB MED	KEEP RIGHT EXCEPT TO PASS	1	48	60	20.00						2												2	220.4										146	
33.778 SB MED		1	36	36	9.00						2					X		2															R3-4		
												FT	FT	FT	FT 9.5	FT 95.2	FT		EA.	LB	LB	LB		LB 1423.5	LB 459.0	LB	LB								
SUBTOTALS SHEET 19		SF 169.50	SF 64.00	EA.	SF							FT			FT 104.7					LB			EA. 17	LB 1882.5				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: **GUILFORD-ROCKINGHAM**
PROJECT NUMBER: **IMG SIGN(44)**

FILE NAME: z12A528tssml.xlsb
PROJECT LEADER: C. GREGORY
DESIGNED BY: J. SMITH
PLOT DATE: 4/16/2014
DRAWN BY: J. SMITH
CHECKED BY: D. MUNRO
TRAFFIC SIGN SUMMARY SHEET 19
SHEET 76 OF 157