STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 20

SHSM = FHWA 2004 STANDARD HIGHWAY SIGNS AND MARKINGS BOOK AND THE 2012 SUPPLEMENT TO THE 2004 EDITION

MILE MARKER, DIRECTION	SIGN LEGEND	SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																	REMARKS	SIGN DETAIL		
											NO. OF POSTS	FLANGED CHANNEL lb/ft			SQUARE STEEL (in) lb/ft			ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (in) lb/ft			FND-ATION	TUBULAR STEEL DIA (in) lb/ft				W-SHAPE STEEL FTG. SIZE		WEIGHT	POST SIZE	SIGN FRAME		SHSM	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
		EA.	WIDTH (in)	HEIGHT (in)	"A"	"B"	SALV SIGN	SALV TIS	RETAIN	SALVAGE		1.12	2.0	3.0	1.75	2.0	2.5			3.0	4.0	4.0Mod		3.0	3.5	4.0	5.0	24"	30"							
															1.88	2.42	3.35			1.3	1.7	1.7		7.6	9.0	10.8	14.6									
33.014 SB		1	48	48	16.00						2												2	205.2									VW-285		146	
31.295 SB	ENTERING TOWN OF WESTMINSTER	1	36	24	6.00						2					X		2																		E-131
31.257 SB	BRIDGE ICES BEFORE ROAD	1	48	48	16.00						2												2	205.2										W8-13		
31.119 SB	Saxtons River	1	48	28	9.33						2					X		2																		147	
31.114 SB		1	12	36	3.00						1					X		1																	OM-3R		
31.105 SB MED		1	12	36	3.00						1					X		1																	OM-3L		
30.739 SB MED		1	36	36	9.00						2					X		2																	R3-4		
30.696 SB MED		1	36	36	9.00						2					X		2																	R3-4		
29.627 SB	EXIT 5	1	96	30	20.00																															143	
	TO 5 123 Westminster Walpole NH 1 MILE	1	204	144		204.00					2																		2		805	W8X21			THINNING AND TRIMMING Fuse-Plate Bolt Tension 33.9 kips		143	
29.210 SB	EXIT 5	1	96	30	20.00																															143	
	TO 5 123 Westminster Walpole NH ½ MILE	1	204	144		204.00																														143	
	NEXT EXIT 12 MILES	1	150	24		25.00					2																		2		1124	W10X26			THINNING AND TRIMMING Fuse-Plate Bolt Tension 31.2 kips Special Provision Footing (2); See Sht 3	E2-1P		
29.063 SB MED		1	36	36	9.00						2					X		2																	R3-4		
29.060 SB	NEXT RIGHT	1	144	144		144.00					2																		2		733	W8X18			THINNING AND TRIMMING Fuse-Plate Bolt Tension 19.9 kips Special Provision Footing (2); See Sht 3		142	
											FT	FT	FT	FT	FT	185.9	FT	EA.	LB	LB	LB		LB 410.4	LB	LB	LB									
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".	SUBTOTALS SHEET 20	SF 120.33	SF 577.00	EA.	SF		FT			FT 185.9			LB		EA. 4	LB 410.4				EA. 6	EA.	LB 2662										

PROJECT NAME: **GUILFORD-ROCKINGHAM**
PROJECT NUMBER: **IMG SIGN(44)**

FILE NAME:	z12A528tssml.xlsb	PLOT DATE:	4/16/2014
PROJECT LEADER:	C. GREGORY	DRAWN BY:	J. SMITH
DESIGNED BY:	J. SMITH	CHECKED BY:	D. MUNRO
TRAFFIC SIGN SUMMARY SHEET 20		SHEET	77 OF 157