STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 22

SHSM = FHWA 2004 STANDARD HIGHWAY SIGNS AND MARKINGS BOOK AND THE 2012 SUPPLEMENT TO THE 2004 EDITION

MILE MARKER, DIRECTION	SIGN LEGEND	SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																					REMARKS	SIGN DETAIL		
		EA.	WIDTH (in)	HEIGHT (in)	"A"	"B"	SALV SIGN	SALV TIS	RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft			SQUARE STEEL (in) lb/ft			ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (in) lb/ft				TUBULAR STEEL DIA (in) lb/ft					W-SHAPE STEEL				SIGN FRAME		SHSM	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												1.12	2.0	3.0	1.75	2.0	2.5			3.0	4.0	4.0Mod	FND-ATION	3.0	3.5	4.0	5.0	FTG. SIZE 24"	FTG. SIZE 30"	WEIGHT	POST SIZE					
															1.88	2.42	3.35			1.3	1.7	1.7		7.6	9.0	10.8	14.6									
27.888 SB	Putney 11 Brattleboro 20	1	120	36		30.00					2												2	237.2									THINNING AND TRIMMING		143	
27.632 SB	KEEP RIGHT EXCEPT TO PASS	1	48	60	20.00						2												2	220.4											146	
27.632 SB MED	KEEP RIGHT EXCEPT TO PASS	1	48	60	20.00						2												2	220.4											146	
26.365 SB MED		1	36	36	9.00						2					X		2																R3-4		
24.845 SB	PARKING AREA 1 MILE	1	150	60		62.50					2												2			300.3							THINNING AND TRIMMING		141	
24.486 SB MED		1	36	36	9.00						2					X		2																R3-4		
24.160 SB	PARKING AREA NEXT RIGHT	1	150	60		62.50					2												2				408.8						THINNING AND TRIMMING		141	
23.844 SB		1	18	18	2.25						1				X			1																OM1-1		
23.841 SB	PARKING AREA	1	90	78		48.75																														141	
	WRONG WAY	1	42	30	8.75						2												2			291.6							BACK TO BACK	R5-1a		
23.800 SB		1	48	48	16.00						2												2	205.2										W4-1R		
23.757 SB MED	ONE WAY	1	54	18	6.75						2					X		2																R6-1R		
23.550 SB	ENTERING TOWN OF PUTNEY	1	36	24	6.00						2					X		2																		E-131
23.020 SB MED		1	36	36	9.00						2					X		2																R3-4		
23.005 SB	WEIGH STATION 1 MILE	1	96	72		48.00					2												2		242.1								THINNING AND TRIMMING		141	
22.709 SB	ALL TRUCKS NEXT RIGHT	1	114	48		38.00																	2										THINNING & TRIMMING		141	
	WHEN FLASHING	1	114	30		23.75					2												2				436.6								141	
												FT	FT	FT	FT	FT	FT	EA.		LB	LB	LB		LB	LB	LB	LB									
															9.5	158.8								883.2	242.1	591.9	845.4									
SUBTOTALS SHEET 22		SF	SF	EA.	SF							FT			FT					LB			EA.	LB				EA.	EA.							
		106.75	313.50												168.3								18	2562.6												

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: **GUILFORD-ROCKINGHAM**
PROJECT NUMBER: **IMG SIGN(44)**

FILE NAME: **z12A528tssml.xlsb** PLOT DATE: **4/15/2014**
PROJECT LEADER: **C. GREGORY** DRAWN BY: **J. SMITH**
DESIGNED BY: **J. SMITH** CHECKED BY: **D. MUNRO**
TRAFFIC SIGN SUMMARY SHEET 22 SHEET **79** OF **157**