STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 35

SHSM = FHWA 2004 STANDARD HIIGHWAY SIGNS AND MARKINGS BOOK AND THE 2012 SUPPLEMENT TO THE 2004 EDITION

MILE MARKER, DIRECTION	SIGN LEGEND	SIGN DIMENSIONS EA.	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (in) 3.0 lb/ft 1.3	4.0 1.7	4.0Mod 1.7	TUBULAR STEEL DIA (in) FND-ATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL SHSM	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
INT #1 0.032 RAMP D RT	PROHIBITED PEDESTRIANS BICYCLES SLOW MOVING VEHICLES FARM MACHINERY SNOW VEHICLES	1	36	36	9.00																															E-142
	TURN SIGNAL REQUIRED BEFORE CHANGING LANES	1	36	36	9.00						2												2	191.6											E-142
0.041-0.071 LT RAMP D		5	24	30	25.00						5					X		5															FLUORESCENT YELLOW TYPE IX SHEETING	W1-8		
0.132 RAMP D RT	20 MPH	1 1	36 18	36 18	9.00 2.25						2					X		2																W1-11 W13-1		
0.166-0.226 LT RAMP D		5	24	30	25.00						5					X		5															FLUORESCENT YELLOW TYPE IX SHEETING	W1-8		
0.236 RAMP D RT		1	30	30	6.25						~~1~~ 2					X		~~1~~ 2															THINNING & TRIMMING	R3-2		
0.060 RAMP E RT		1	36	36	9.00						2					X		2																W3-1		
0.096 RAMP E RT	SOUTH NORTH TO	1 1 1	24 24 24	12 12 12	2.00 2.00 2.00																												BLACK ON WHITE BLACK ON WHITE GREEN ON WHITE	M3-3 M3-1 M4-5		
	5 5 VERMONT 142	1 1 1	24 24 30	24 24 24	4.00 4.00 5.00																												THINNING & TRIMMING	M1-4 M1-4		E-136B
		1 1 1	21 21 21	15 15 15	2.19 2.19 2.19						2												2	195.4									#3B	BLACK ON WHITE BLACK ON WHITE GREEN ON WHITE	M6-1 M6-1 M6-1		
0.134 RAMP E RT	Guilford I Brattleboro 2	1 1	72 72	12 12	6.00 6.00																													148 148	
	Vernon 8 Hinsdale NH 8	1 1	72 72	12 12	6.00 6.00						2												2	206.8										THINNING & TRIMMING	148 148		
0.172 RAMP E RT	SERVICES HOSPITAL I CAMPING 2	1 1 1	72 72 72	10 10 10	5.00 5.00 5.00																													148 148 148	
	WRONG WAY	1	36	24	6.00						2												2	168.8										THINNING & TRIMMING BACK TO BACK	R5-1a		
											FT	FT	FT		FT	FT 232.6	FT	EA.		LB	LB	LB		LB 762.6	LB	LB	LB									

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

SUBTOTALS SHEET 35	SF 165.07	SF	EA.	SF		FT	FT 232.6	LB	EA. 8	LB 762.6	EA.	EA.	LB

PROJECT NAME: GUILFORD-ROCKINGHAM
PROJECT NUMBER: IMG SIGN(44)

FILE NAME: z12A528tssint.xlsb
PROJECT LEADER: C. GREGORY
DESIGNED BY: J. SMITH
TRAFFIC SIGN SUMMARY SHEET 35

PLOT DATE: 4/16/2014
DRAWN BY: J. SMITH
CHECKED BY: D. MUNRO
SHEET 92 OF 157