STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 36

SHSM = FHWA 2004 STANDARD HIGHWAY SIGNS AND MARKINGS BOOK AND THE 2012 SUPPLEMENT TO THE 2004 EDITION

MILE MARKER, DIRECTION	SIGN LEGEND	SIGN DIMENSIONS EA.	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75	2.0	2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (in) 3.0	4.0	4.0Mod	FND-ATION	TUBULAR STEEL DIA (in) 3.0	3.5	4.0	5.0	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL SHSM	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												lb/ft			lb/ft					lb/ft				lb/ft													
INT #1 0.172 RAMP E LT	WRONG WAY	1	36	24	6.00						2					X		2																R5-1a		
0.212 RAMP E LT	STOP / DO NOT ENTER	1	30	30	6.25																											BACK TO BACK	R1-1		
		1	30	30	6.25																												R5-1		
	ONE WAY / ONE WAY	1	36	12	3.00						1					X		1														BACK TO BACK	R6-1L		
		1	36	12	3.00																												R6-1R		
0.216 RAMP E LT	STOP / DO NOT ENTER	1	30	30	6.25																											BACK TO BACK	R1-1		
		1	30	30	6.25																												R5-1		
	ONE WAY / ONE WAY	1	36	12	3.00						1					X		1														BACK TO BACK	R6-1L		
		1	36	12	3.00																												R6-1R		
0.217 RAMP E LT	SOUTH / NORTH / TO	1	24	12	2.00																											BLACK ON WHITE	M3-3		
		1	24	12	2.00																											BLACK ON WHITE	M3-1		
		1	24	12	2.00																											GREEN ON WHITE	M4-5		
	5 / 5 / VERMONT 142	1	24	24	4.00																												M1-4		
		1	24	24	4.00																												M1-4		
		1	30	24	5.00																														E-136B
		1	21	15	2.19																											BLACK ON WHITE	M6-1		
		1	21	15	2.19						2												2	180.2							#3B	BLACK ON WHITE	M6-1		
		1	21	15	2.19																											GREEN ON WHITE	M6-1		
0.217 RAMP E RT	STOP / DO NOT ENTER	1	30	30	6.25																											BACK TO BACK	R1-1		
		1	30	30	6.25																												R5-1		
	ONE WAY / ONE WAY	1	36	12	3.00						1					X		1														BACK TO BACK	R6-1L		
		1	36	12	3.00																												R6-1R		
0.040-0.055 LT RAMP H		3	24	30	15.00						3					X		3														FLUORESCENT YELLOW TYPE IX SHEETING	W1-8		
0.068 RAMP H LT	YIELD	1			3.90						1					X		1														36" X 36" X 36"	R1-2		
0.068 RAMP H RT	YIELD	1			3.90						1					X		1														36" X 36" X 36"	R1-2		
												FT	FT	FT	FT	FT 148.0	FT	EA.		LB	LB	LB		LB 180.2	LB	LB	LB									
SUBTOTALS SHEET 36		SF 109.87	SF	EA.	SF							FT			FT 148.0					LB			EA. 2	LB 180.2				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: **GUILFORD-ROCKINGHAM**
PROJECT NUMBER: **IMG SIGN(44)**

FILE NAME: **z12A528tssint.xlsb** PLOT DATE: **4/16/2014**
PROJECT LEADER: **C. GREGORY** DRAWN BY: **J. SMITH**
DESIGNED BY: **J. SMITH** CHECKED BY: **D. MUNRO**
TRAFFIC SIGN SUMMARY SHEET 36 SHEET **93** OF **157**