STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 41

SHSM = FHWA 2004 STANDARD HIIGHWAY SIGNS AND MARKINGS BOOK AND THE 2012 SUPPLEMENT TO THE 2004 EDITION

MILE MARKER, DIRECTION	SIGN LEGEND	SIGN DIMENSIONS EA.	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (in) 3.0 lb/ft 1.3	4.0 1.7	4.0Mod 1.7	TUBULAR STEEL DIA (in) FND-ATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL SHSM	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
INT #2	GAS	1	72	10	5.00																															148	
0.048 RAMP CD LT	DIESEL 1	1	72	10	5.00																															148	
	FOOD 3	1	72	10	5.00																															148	
	LODGING 2	1	72	10	5.00																															148	
	STATE POLICE 3	1	72	10	5.00																															148	
	WRONG WAY	1	36	24	6.00						2												2	194.6									BACK TO BACK	R5-1a		
0.014 RAMP CD LT ISLAND		1	18	18	2.25						1				X			1																OM1-1		
0.011 RAMP CD LT	YIELD STOP	1	30	30	6.25 3.90						1					X		1																PAY BOTH YEILD & STOP SIGN QTY. 36"X36"X36"	R1-2		
0.010 RAMP CD LT ISLAND	STOP DO NOT ENTER	1	30	30	6.25																													BACK TO BACK	R1-1		
		1	30	30	6.25																														R5-1		
	ONE WAY ONE WAY	1	36	12	3.00						1					X		1																BACK TO BACK	R6-1L		
		1	36	12	3.00																														R6-1R		
0.012 RAMP CD CL	STOP	1	30	30	6.25																													BACK TO BACK	R1-1		
		1	24	30	5.00																														R4-7		
		1	18	18	2.25						1					X		1	1															BACK TO BACK	OM1-1		
		1	18	18	2.25																														OM1-1		
0.069 RAMP CD CL		1	24	30	5.00																														R4-7		
		1	18	18	2.25						1					X		1	1															BACK TO BACK	OM1-1		
		1	18	18	2.25																														OM1-1		
0.259 RAMP CD CL		1	24	30	5.00		1																												R4-7		
		1	18	18	2.25		3				1					X		1	1															BACK TO BACK	OM1-1		
		1	18	18	2.25																														OM1-1		
0.030-.091 LT RAMP C		5	24	30	25.00						5					X		5																FLUORESCENT YELLOW TYPE IX SHEETING	W1-8		
0.108 RAMP C RT		1	30	30	6.25						2					X		2																	R3-2		
												FT	FT	FT	FT 9.5	FT 160.9	FT		EA. 3	LB	LB	LB		LB 194.6	LB	LB	LB									
SUBTOTALS SHEET 41		SF 121.65	SF	EA.	SF							FT			FT 170.4					LB			EA. 2	LB 194.6				EA.	EA.	LB						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD.
POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: **GUILFORD-ROCKINGHAM**
PROJECT NUMBER: **IMG SIGN(44)**

FILE NAME: **z12A528tssint.xlsb** PLOT DATE: **4/16/2014**
PROJECT LEADER: **C. GREGORY** DRAWN BY: **J. SMITH**
DESIGNED BY: **J. SMITH** CHECKED BY: **D. MUNRO**
TRAFFIC SIGN SUMMARY SHEET 41 SHEET **98** OF **157**