STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 46

SHSM = FHWA 2004 STANDARD HIGHWAY SIGNS AND MARKINGS BOOK AND THE 2012 SUPPLEMENT TO THE 2004 EDITION

MILE MARKER, DIRECTION	SIGN LEGEND	SIGN DIMENSIONS EA.	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75	2.0	2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (in) 3.0	4.0	4.0Mod	FND-ATION	TUBULAR STEEL DIA (in) 3.0	3.5	4.0	5.0	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL SHSM	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												lb/ft			lb/ft					lb/ft				lb/ft												
INT #4	STOP / DO NOT ENTER	1	30	30	6.25																												BACK TO BACK	R1-1		
0.179 RAMP B RT		1	30	30	6.25																													R5-1		
	ONE WAY / ONE WAY	1	36	12	3.00						1						X	1															BACK TO BACK	R6-1L		
		1	36	12	3.00																													R6-1R		
0.181 RAMP B LT	STOP /	1	30	30	6.25																												BACK TO BACK	R1-1		
		1	24	30	5.00																													R4-7		
		1	18	18	2.25						1					X		1	1														BACK TO BACK	OM1-1		
		1	18	18	2.25																													OM1-1		
0.075 RAMP C RT		1	36	36	9.00						2					X		2																W3-1		
0.112 RAMP C RT	Putney / Landmark College	1	72	12	6.00																														148	
		1	72	12	6.00																														148	
	TO	1	24	12	2.00																												BLACK ON WHITE	M4-5		
	5	1	24	24	4.00																													M1-4		
		1	21	15	2.19						2												2	210.6								BLACK ON WHITE	M6-1		
0.150 RAMP C RT	GAS/DIESEL 24HR / FOOD	1	72	10	5.00																														148	
		1	72	10	5.00																														148	
	LODGING / INFORMATION	1	72	10	5.00																														148	
		1	72	10	5.00																														148	
	3 CAMPING	1	72	10	5.00																														148	
	WRONG WAY	1	36	24	6.00						2												2	179.4								BACK TO BACK	R5-1a		
0.150 RAMP C LT	WRONG WAY	1	36	24	6.00						2					X		2																R5-1a		
												FT	FT	FT	FT	FT	FT	EA.		LB	LB	LB		LB	LB	LB	LB									
																76.0	15.1	1						390.0												
SUBTOTALS SHEET 46		SF	SF	EA.	SF							FT			FT					LB			EA.	LB				EA.	EA.	LB					
		100.44													91.1								4	390.0											

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: **GUILFORD-ROCKINGHAM**
PROJECT NUMBER: **IMG SIGN(44)**

FILE NAME: **z12A528tssint.xlsb** PLOT DATE: **4/16/2014**
PROJECT LEADER: **C. GREGORY** DRAWN BY: **J. SMITH**
DESIGNED BY: **J. SMITH** CHECKED BY: **D. MUNRO**
TRAFFIC SIGN SUMMARY SHEET 46 SHEET **103** OF **157**