STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 47

SHSM = FHWA 2004 STANDARD HIIGHWAY SIGNS AND MARKINGS BOOK AND THE 2012 SUPPLEMENT TO THE 2004 EDITION

MILE MARKER, DIRECTION	SIGN LEGEND	SIGN DIMENSIONS EA.	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (in) 3.0 lb/ft 1.3	4.0 1.7	4.0Mod 1.7	TUBULAR STEEL DIA (in) FND-ATION	3.0 lb/ft 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL SHSM	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
INT #4		1	30	30	6.25																													R1-1		
0.188 RAMP C LT	STOP / DO NOT ENTER	1	30	30	6.25																												BACK TO BACK	R5-1		
		1	36	12	3.00						1					X		1															R6-1L		
	ONE WAY / ONE WAY	1	36	12	3.00																												BACK TO BACK	R6-1R		
0.188 RAMP C RT	STOP / DO NOT ENTER	1	30	30	6.25																												BACK TO BACK	R1-1		
		1	30	30	6.25																													R5-1		
	ONE WAY / ONE WAY	1	36	12	3.00						1					X		1															BACK TO BACK	R6-1L		
		1	36	12	3.00																													R6-1R		
0.030 RAMP D RT	PROHIBITED ...	1	36	36	9.00																												THINNING & TRIMMING			E-142
	TURN SIGNAL REQUIRED BEFORE CHANGING LANES	1	36	36	9.00						2												2	191.6											E-142
0.077 RAMP D RT		1	30	30	6.25						1					X		1																R3-2		
0.015 PSH RT	JCT	1	21	15	2.19																												(INTERSTATE) WHITE ON BLUE	M2-1		
	INTERSTATE 91	1	24	24	4.00						1					X		1																M1-1		
0.115 PSH RT	JCT	1	21	15	2.19																												BLACK ON WHITE	M2-1		
	5	1	24	24	4.00						1					X		1																M1-4		
0.222 PSH RT	Putney / Brattleboro 11	1	72	12	6.00						2												2	126.2											148	
		1	72	12	6.00																														148	
0.245 PSH RT	FOOD / GAS/DIESEL 24HR	1	72	10	5.00																														148	
		1	72	10	5.00																														148	
	3 CAMPING	1	72	10	5.00						2												2	184.0											148	
												FT	FT	FT	FT	FT 73.1	FT	EA.		LB	LB	LB		LB 501.8	LB	LB	LB								
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".	SUBTOTALS SHEET 47	SF 100.63	SF	EA.	SF							FT			FT 73.1					LB			EA. 6	LB 501.8				EA.	EA.	LB					

PROJECT NAME: **GUILFORD-ROCKINGHAM**
PROJECT NUMBER: **IMG SIGN(44)**

FILE NAME: z12A528tssint.xlsb
PROJECT LEADER: C. GREGORY
DESIGNED BY: J. SMITH
TRAFFIC SIGN SUMMARY SHEET 47

PLOT DATE: 4/16/2014
DRAWN BY: J. SMITH
CHECKED BY: D. MUNRO
SHEET 104 OF 157