STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 48

SHSM = FHWA 2004 STANDARD HIIGHWAY SIGNS AND MARKINGS BOOK AND THE 2012 SUPPLEMENT TO THE 2004 EDITION

MILE MARKER, DIRECTION	SIGN LEGEND	SIGN DIMENSIONS EA.	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0Mod lb/ft 1.7	TUBULAR STEEL DIA (in) FND-ATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL SHSM	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
INT #4 0.268 PSH RT	TO	1	24	12	2.00																												(INTERSTATE) WHITE ON BLUE	M4-5		
	SOUTH SOUTH NORTH	1	24	12	2.00																												BLACK ON WHITE	M3-3		
		1	24	12	2.00																												(INTERSTATE) WHITE ON BLUE	M3-3		
		1	24	12	2.00																												BLACK ON WHITE	M3-1		
	5 INTERSTATE 91 5	1	24	24	4.00																													M1-4		
		1	24	24	4.00																													M1-1		
		1	24	24	4.00																													M1-4		
		1	21	15	2.19																												BLACK ON WHITE	M6-1		
		1	21	15	2.19						2												2	195.4							#3A	(INTERSTATE) WHITE ON BLUE	M6-1		
		1	21	15	2.19																												BLACK ON WHITE	M6-3		
0.281 PSH RT	STOP	1	30	30	6.25		I				1					X		1																R1-1		
0.200 PSH LT	Bellows Falls 14 White River Jct 53	1	72	12	6.00						2												2	130.8										148		
		1	72	12	6.00																													148		
0.156 PSH LT	NORTH	1	24	12	2.00																												(INTERSTATE) WHITE ON BLUE	M3-1		
	INTERSTATE 91	1	24	24	4.00																													M1-1		
		1	21	15	2.19						1						X	1															(INTERSTATE) WHITE ON BLUE	M5-1		
0.044 PSH RT SLIP RAMP	STOP DO NOT ENTER	1	30	30	6.25		I				1					X		1															BACK TO BACK	R1-1		
		1	30	30	6.25																													R5-1		
0.035 PSH LT SLIP RAMP	DO NOT ENTER	1	30	30	6.25						1					X		1																R5-1		
5.060 US 5 RT DUMMERSTON	JCT	1	21	15	2.19																												(INTERSTATE) WHITE ON BLUE	M2-1		
	INTERSTATE 91	1	24	24	4.00						1					X		1																M1-1		
												FT	FT	FT	FT	FT 57.2	FT 15.9	EA.		LB	LB	LB		LB 326.2	LB	LB	LB								
		SUBTOTALS SHEET 48	SF 77.95	SF	EA.	SF						FT			FT 73.1					LB			EA. 4	LB 326.2				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: **GUILFORD-ROCKINGHAM**
PROJECT NUMBER: **IMG SIGN(44)**

FILE NAME: **z12A528tssint.xlsb** PLOT DATE: **4/16/2014**
PROJECT LEADER: **C. GREGORY** DRAWN BY: **J. SMITH**
DESIGNED BY: **J. SMITH** CHECKED BY: **D. MUNRO**
TRAFFIC SIGN SUMMARY SHEET 48 SHEET **105** OF **157**